RFP C24-01 GROVES ATHLETIC FIELDS & FIELDHOUSE

100 PRISCILLA D. THOMAS WAY
SAVANNAH, GA 31408

BID SET
07/12/2023
5201-192070

SAVANNAH-CHATHAM COUNTY PUBLIC SCHOOL SYSTEM

RFP C24-01 GROVES ATHLETIC FIELDS & FIELDHOUSE

SHEET INDEX SET D

GENERAL

SHEET NO.	SHEET NAME	SHT REV NO.	SHT REV DATE	REVISION DESCRIPTION
G-000	COVER SHEET			
G-001	INDEX SHEET	3	07/21/23	Addendum 7
G-002	PROJECT INFORMATION SHEET			
G-100	U.L. DETAILS			
G-101	U.L. DETAILS			
G-102	DETAILS - FIRE RATED/ LIFE SAFETY			
G-103	DETAILS - FIRE RATED/ LIFE SAFETY			
G-104	1ST FLOOR LIFE SAFETY PLAN	1	07/12/23	Addendum 5
G-105	2ND FLOOR LIFE SAFETY PLAN	1	07/12/23	Addendum 5

CIVIL

MOFFATT & NICHOL
2 E BRYAN ST, SUITE 501
SAVANNAH, GA 31401
tel: 912.231.0044
email: czuck@moffattnichol.com

LANDSCAPE

CLH DESIGN, P.A.
400 REGENCY FOREST DR, SUITE 120
CARY, NC 27518
tel: 919.319.6716
email: chilt@clhdesignpa.com

STRUCTURAL

THARPE ENGINEERING GROUP
321 W CONGRESS ST, SUITE 301C
SAVANNAH, GA 31401
tel: 912.349.7603
email: bsapp@tharpeengineering.com

SHEET NO.	SHEET NAME	SHT REV NO.	SHT REV DATE	REVISION DESCRIPTION
S-001	GENERAL NOTES, ABBREVS & LEGEND			
S-002	GENERAL NOTES			
S-003	GENERAL NOTES, COMPONENTS & CLADDING			
S-101	FIELDHOUSE FOUNDATION PLAN	1	07/12/2023	Addendum #5
S-201	FIELDHOUSE 2nd FLOOR FRAMING PLAN			
S-202	FIELDHOUSE ROOF FRAMING PLAN			
S-211	CONCESSION/ RESTROOM PLANS	1	07/12/2023	Addendum #5
S-301	FOUNDATION DETAILS	1	07/12/2023	Addendum #5
S-302	FOUNDATION DETAILS			
S-303	FOUNDATION DETAILS			
S-401	MASONRY & FRAMING DETAILS			
S-402	MASONRY & FRAMING DETAILS			
S-403	MASONRY & FRAMING DETAILS			
S-404	MASONRY & FRAMING DETAILS			
S-501	STAIR DETAILS			
S-601	HOLLOWCORE DETAILS			

ARCHITECTURAL

LS3P
321 W. CONGRESS ST, SUITE 301
SAVANNAH, GA 31401
tel: 704.333.6686
email: aprilmundy@ls3p.com

SHEET NO.	SHEET NAME	SHT REV NO.	SHT REV DATE	REVISION DESCRIPTION
A-001	ARCHITECTURAL SITE PLAN			
A-002	ARCHITECTURAL SITE PLAN - ENLARGED	2	07/20/23	Addendum 6
A-003	ARCHITECTURAL SITE PLAN - SOUTH			
A-004	CONSTRUCTION SUBSYSTEMS			
A-005	CONSTRUCTION SUBSYSTEMS CONT.	3	07/21/23	Addendum 7
A-006	PARTITION TYPES			
A-101	1ST FLOOR PLAN - FIELDHOUSE	3	07/21/23	Addendum 7
A-101D	1ST FLOOR PLAN - FIELDHOUSE - DIM	2	07/20/23	Addendum 6
A-102	2ND FLOOR PLAN - FIELDHOUSE	2	07/20/23	Addendum 6
A-102D	2ND FLOOR PLAN - FIELDHOUSE - DIM			
A-103	1ST FLOOR PLAN - RESTROOM / CONCESSIONS			
A-131	1ST FLOOR REFLECTED CEILING PLANS			
A-132	2ND FLOOR REFLECTED CEILING PLAN	2	07/20/23	Addendum 6
A-161	ROOF PLAN	2	07/20/23	Addendum 6
A-201	EXTERIOR ELEVATIONS - FIELDHOUSE	2	07/20/23	Addendum 6
A-202	EXTERIOR ELEVATIONS - FIELDHOUSE			
A-203	EXTERIOR ELEVATIONS AND BUILDING SECTIONS - RESTROOM			
A-301	BUILDING SECTIONS			
A-351	WALL SECTIONS			
A-352	WALL SECTIONS			
A-401	ENLARGED RESTROOM PLANS & ELEVATIONS	2	07/20/23	Addendum 6
A-402	ENLARGED RESTROOM PLANS & ELEVATIONS			
A-403	ENLARGED RESTROOM PLANS & ELEVATIONS	1	07/12/23	Addendum 5
A-404	INTERIOR CORRIDOR ELEVATIONS			
A-405	ENLARGED ENTRY WALL & RAILING PLANS & ELEVATIONS			
A-406	ACCESS ROAD PLAN			
A-421	STAIR AND ELEVATOR PLANS & SECTIONS			
A-506	ARCHITECTURAL CAST STONE TYPICAL DETAILS			
A-511	PLAN AND SECTION DETAILS			
A-512	SECTION DETAILS			
A-521	CEILING & SEISMIC DETAILS			
A-540	LOCKER & TOILET STALL DETAILS	2	07/20/23	Addendum 6
A-551	ROOF DETAILS			
A-552	ROOF DETAILS			
A-600	DOOR SCHEDULE, DOOR & FRAME TYPE LEGEND	3	07/21/23	Addendum 7
A-608	HEAD, JAMB, AND SILL DETAILS - HM AND INT. STOREFRONT			
A-609	HEAD, JAMB, AND SILL DETAILS - WINDOW WALL			
A-610	FRAME ELEVATIONS	2	07/20/23	Addendum 6
A-611	DOOR & SECURITY HARDWARE PLAN - 1ST FLOOR	3	07/21/23	Addendum 7
A-612	DOOR & SECURITY HARDWARE PLAN - 2ND FLOOR	3	07/21/23	Addendum 7
A-613	THRESHOLD DETAILS			
A-614	SIGNAGE ELEVATIONS			
A-700	ROOM FINISH LEGEND AND NOTES	2	07/20/23	Addendum 6
A-701	1ST FLOOR FINISH PLAN	1	07/12/23	Addendum 5
A-702	2ND FLOOR FINISH PLAN	1	07/12/23	Addendum 5
A-703	1ST FLOOR FINISH PLAN - RESTROOM / CONCESSIONS	1	07/12/23	Addendum 5
A-770	CASEWORK & SPECIALTY EQUIPMENT LEGENDS & DETAILS	2	07/20/23	Addendum 6
A-771	CASEWORK ELEVATIONS	1	07/12/23	Addendum 5
A-800	MISC DETAILS	3	07/21/23	Addendum 7
A-801	MISC DETAILS	3	07/21/23	Addendum 7
A-802	MISC DETAILS	3	07/21/23	Addendum 7

2

FIRE PROTECTION

DULOHERY WEEKS
7402 HODGSON MEMORIAL DR, SUITE 100
SAVANNAH, GA 31406
tel: 912.355.0235
email: JSwails@dulohery.com

SHEET NO.	SHEET NAME	SHT REV NO.	SHT REV DATE	REVISION DESCRIPTION
F-101	1st FLOOR FIRE PROTECTION PLAN - FIELDHOUSE			
F-102	2nd FLOOR FIRE PROTECTION PLAN - FIELDHOUSE			

PLUMBING

DULOHERY WEEKS
7402 HODGSON MEMORIAL DR, SUITE 100
SAVANNAH, GA 31406
tel: 912.355.0235
email: JSwails@dulohery.com

SHEET NO.	SHEET NAME	SHT REV NO.	SHT REV DATE	REVISION DESCRIPTION
P-001	PLUMBING LEGEND, SCHEDULES & DETAILS			
P-101	1st FLOOR DRAINAGE & VENT PLAN - FIELDHOUSE			
P-102	2nd FLOOR DRAINAGE & VENT PLAN - FIELDHOUSE			
P-103	1ST FLOOR DRAINAGE & VENT PLAN - RESTROOM / CONCESSIONS			
P-201	1st FLOOR HOT & COLD WATER PLAN - FIELDHOUSE			
P-202	2nd FLOOR HOT & COLD WATER PLAN - FIELDHOUSE			
P-203	1ST FLOOR HOT & COLD WATER PLAN - RESTROOM / CONCESSIONS			
P-301	PLUMBING ROOF PLAN - FIELDHOUSE			
P-401	PLUMBING DETAILS			

MECHANICAL

DULOHERY WEEKS
7402 HODGSON MEMORIAL DR, SUITE 100
SAVANNAH, GA 31406
tel: 912.355.0235
email: JSwails@dulohery.com

SHEET NO.	SHEET NAME	SHT REV NO.	SHT REV DATE	REVISION DESCRIPTION
M-001	MECHANICAL LEGEND & SCHEDULES			
M-101	1ST FLOOR MECHANICAL PLAN - FIELDHOUSE			
M-102	2ND FLOOR MECHANICAL PLAN - FIELDHOUSE			
M-103	1ST FLOOR MECHANICAL PLAN - RESTROOM / CONCESSIONS			
M-200	MECHANICAL ROOF PLAN			
M-400	MECHANICAL DETAILS			
M-401	MECHANICAL DETAILS			

ELECTRICAL

DULOHERY WEEKS
7402 HODGSON MEMORIAL DR, SUITE 100
SAVANNAH, GA 31406
tel: 912.355.0235
email: JSwails@dulohery.com

SHEET NO.	SHEET NAME	SHT REV NO.	SHT REV DATE	REVISION DESCRIPTION
E-000	ELECTRICAL SCHEDULE & LEGEND	2	07/12/2023	ADDENDUM 5
E-001	LIGHTING DETAILS			
E-002	ELECTRICAL SITE PLAN			
E-003	ELECTRICAL SITE PLAN - STADIUM FIELD HOUSE AND POLICE ANNEX	1		
E-101	LIGHTING PLAN - FIELDHOUSE			
E-102	LIGHTING PLAN - RESTROOM / CONCESSIONS			
E-201	POWER PLAN - FIELDHOUSE	1		
E-202	POWER PLAN - RESTROOM / CONCESSIONS			
E-301	MECHANICAL POWER - FEILDHOUSE			
E-302	ELECTRICAL ROOF PLAN - FIELDHOUSE			
E-303	MECHANICAL POWER - RESTROOM / CONCESSIONS			
E-401	FIRE ALARM PLAN - FIELD HOUSE	1		
E-402	FIRE ALARM PLAN - RESTROOM / CONCESSIONS			
E-501	ENLARGED DATA ROOMS			
E-601	FIELDHOUSE POWER RISER DIAGRAM	2	07/12/2023	ADDENDUM 5
E-602	POWER RISER DETAILS			
E-603	PANEL SCHEDULES	1		
E-604	PANEL SCHEDULES			
E-701	ELECTRICAL DETAILS	2	07/12/2023	ADDENDUM 5
E-800	EXTERIOR LIGHTING ELEVATIONS			
E-900	FIELDHOUSE BUILDING			

TELECOM

DULOHERY WEEKS
7402 HODGSON MEMORIAL DR, SUITE 100
SAVANNAH, GA 31406
tel: 912.355.0235
email: JSwails@dulohery.com

T-000	TELECOM LEGEND & GROUNDING/BONDING RISER			
T-001	TELECOM GROUNDING AND BONDING DETAILS			
T-101	CABLE MANAGEMENT - FIELDHOUSE			
T-201	SECURITY SYSTEMS - FIELDHOUSE			
T-202	SECURITY SYSTEMS - RESTROOM / CONCESSIONS			
T-301	TELECOM DETAILS			
T-302	TELECOM DETAILS			

STADIUM DESIGN

CHA
7 E CONGRESS ST, SUITE 306
SAVANNAH, GA 31401
tel: 912.335.8366
email: PGraham@chacompanies.com

SHEET NO.	SHEET NAME	SHT REV NO.	SHT REV DATE	REVISION DESCRIPTION
SR-101	STADIUM TRACK AND FIELD LAYOUT			
SR-201	STADIUM TRACK AND FIELD GRADING PLAN			
SR-301	STADIUM TRACK AND FIELD DRAINAGE PLAN			
SR-501	STADIUM TRACK AND FIELD UTILITY AND IRRIGATION PLAN			
SR-600	SPORTS DETAILS			
SR-601	SPORTS DETAILS			
SR-602	SPORTS DETAILS			
SR-603	SPORTS DETAILS			
SR-604	SPORTS DETAILS			
SR-605	SPORTS DETAILS			
SR-606	SPORTS DETAILS			
SR-607	SPORTS DETAILS			
SR-700	PROJECT DATA, BUILDING CODE, SYMBOLS AND ABBREVIATIONS			
SR-701	HOME (WEST) GRANDSTAND LIFE SAFETY PLANS			
SR-711	HOME (WEST) GRANDSTAND PLANS			
SR-712	VISITOR (EAST) GRANDSTAND PLANS			
SR-721	HOME GRANDSTAND ELEVATIONS			
SR-722	VISITOR GRANDSTAND ELEVATIONS			
SR-723	PRESSBOX ENLARGED ELEVATIONS			
SR-731	BUILDING SECTION			
SR-732	BUILDING SECTION			
SR-733	BUILDING SECTION			
SR-734	BUILDING SECTION			
SR-735	BUILDING SECTION			
SR-740	PRESSBOX ENLARGED PLANS AND DETAILS			
SR-741	OFFICIALS & ELECTRIC ROOM ENLARGED PLANS & DETAILS			
SR-742	OFFICIALS & ELECTRIC ROOM ELEVATIONS & DETAILS			
SR-750	ENLARGED DETAILS			
SR-751	ENLARGED DETAILS			
SR-800	STRUCTURAL NOTES			
SR-801	HOME (WEST) GRANDSTAND FOUNDATION PLAN			
SR-802	VISITOR (EAST) GRANDSTAND FOUNDATION PLAN			
SR-803	PRESS BOX FOUNDATION PLAN AND SECTION			
SR-804	ELECTRIC AND OFFICIALS ROOM FOUNDATION AND FRAMING PLAN			
SR-805	HOME GRANDSTAND ELEVATIONS			
SR-806	VISITOR GRANDSTAND ELEVATIONS			
SR-807	DUGOUT PLANS			
SR-808	FOUNDATION SECTIONS AND DETAILS			
SR-809	FOUNDATION SECTIONS AND DETAILS			
SR-810	FRAMING SECTIONS AND DETAILS			
SR-811	TYPICAL CONCRETE DETAILS			
SR-812	TYPICAL CONCRETE DETAILS			
SR-813	TYPICAL MASONRY DETAILS			
SR-814	TYPICAL MASONRY DETAILS			
SR-815	TYPICAL WOOD DETAILS			
SR-816	TYPICAL STEEL DETAILS			
SE-001	ELECTRICAL GENERAL NOTES			
SE-002	OVERALL ELECTRICAL SITE LAYOUT			
SE-101	STADIUM ELECTRICAL SITE PLAN			
SE-102	SOCCER FIELD ELECTRICAL PLAN			
SE-103	BASEBALL FIELD ELECTRICAL PLAN			
SE-104	YOUTH FIELD ELECTRICAL PLAN			
SE-105	SOFTBALL FIELD ELECTRICAL PLAN			
SE-201	HOME SIDE GRANDSTANDS ELEC AND SYS PLAN			
SE-202	HOME SIDE GRANDSTANDS LIGHTING PLAN			
SE-203	VISITOR SIDE GRANDSTANDS ELEC, LGT, & SYS PLAN			
SE-204	DUGOUT ELECTRICAL AND LIGHTING PLANS			
SE-601	ELECTRICAL ONE-LINE DIAGRAM STADIUM			
SE-602	ELECTRICAL ONE-LINE DIAGRAM FIELDS			
SE-603	PANELBOARD SCHEDULES			
SE-604	LIGHTING AND MECHANICAL SCHEDULES			
SE-605	ELECTRICAL DETAILS			
SM-001	MECHANICAL LEGENDS AND SCHEDULES			
SM-101	OFFICIALS BUILDING MECHANICAL PLAN			
SP-001	PLUMBING LEGENDS, SCHEDULES AND DETAILS			
SP-101	OFFICIALS BUILDING PLUMBING PLANS			

DRAWING SET LEGEND

SET A2 - CIVIL/LANDSCAPE
SET B - K-12 BUILDING (NIC-PREVIOUS PHASE)
SET C - MULTI-MEDIA BUILDING (NIC-PREVIOUS PHASE)
SET D2 - FIELDHOUSE/STADIUM
SET E2 - ATHLETICS

LS3P
321 WEST CONGRESS STREET SUITE 301
SAVANNAH, GEORGIA 31401
TEL. 912.695.2111 FAX 912.298.0206
WWW.LS3P.COM

STATE OF GEORGIA
APRIL W. MUNDY
5/12/2023
CERTIFICATE NO. 013502
REGISTERED ARCHITECT

MEMBERS OF THE AMERICAN INSTITUTE OF ARCHITECTS

COPYRIGHT 2019 ALL RIGHTS RESERVED
PRINTED OR ELECTRONIC DRAWINGS AND DOCUMENTATION MAY NOT BE REPRODUCED IN ANY FORM WITHOUT WRITTEN PERMISSION FROM LS3P ASSOCIATES LTD.

REVISIONS:

No.	Description	Date
3	Addendum 7	07/21/23

PROJECT: 5201-192070
DATE: 07/12/2023
DRAWN BY: KAS
CHECKED BY: AWM

INDEX SHEET

G-001

BID SET

BIM 360://5201-192070 SCCPSS NEW K-12 ATHLETICS/ARCH_GrovesK12_Fieldhouse_NEW.rvt
7/21/2023 1:40:57 PM

S1 TYPICAL SLAB ON GRADE CONSTRUCTION

03 30 00 CAST-IN-PLACE CONCRETE

S2 TYPICAL SECOND FLOOR CONST. [NONCOMBUSTIBLE]

(SEE STRUCTURAL DRAWINGS)
051200.A STEEL BEAM OR
052100.A STEEL JOIST
(SEE STRUCTURAL DRAWINGS)

S3 TYPICAL SECOND FLOOR CONST. [2 HOUR FIRE RATING]

UL D780

033000.A CAST IN PLACE CONCRETE
053100.B FLOOR DECK
(SEE STRUCTURAL DRAWINGS)
SPRAYED FIRE-RESISTANT
078100.B MATERIAL (UL#
051200.A STEEL BEAM OR
052100.A STEEL JOIST
(SEE STRUCTURAL DRAWINGS)

NOT USED

S4 TYPICAL SECOND FLOOR CONST. [2 HOUR FIRE RATING]

UL D902

033000.N CONCRETE SLAB ON STEEL DECK
053100.B FLOOR DECK
(SEE STRUCTURAL DRAWINGS)
078100.B SPRAYED FIRE-RESISTANT MATERIAL
(STRUCTURAL FRAMING ONLY)
051200.A STEEL BEAM OR
052100.A STEEL JOIST
(SEE STRUCTURAL DRAWINGS)

NOT USED

S5 PRE-CAST HOLLOW CORE FLOOR [NONCOMBUSTIBLE]

2" TOPPING SLAB
PRE-CAST CONCRETE HOLLOW
CORE PLANK - SEE STRUCTURAL

S6 PRE-CAST HOLLOW CORE FLOOR [2-HR]

2" TOPPING SLAB
PRE-CAST CONCRETE HOLLOW
CORE PLANK - SEE STRUCTURAL
SPRAYED FIRE-RESISTANT MATERIAL

NOT USED

S7 ATHLETIC WOOD FLOORING SYSTEM

09 64 66 WOOD ATHLETIC FLOORING
03 30 00 CAST-IN-PLACE CONCRETE

REFER TO MANUF. SPECS FOR THICKNESS

NOT USED

S8 STAGE WOOD FLOORING SYSTEM

24" O.C.

3/4 PLYWOOD SUBFLOOR
03 30 00 CAST-IN-PLACE CONCRETE

NOT USED

R1 PVC MEMBRANE / METAL DECK (1 HOUR)

PVC MEMBRANE ROOFING
LIGHTWEIGHT INSULATING CONCRETE
CONTINUOUS RIGID INSULATION, STEPPED AS REQUIRED TO CREATE ROOF SLOPE
CORRUGATED VENTED METAL DECKING - SEE STRUCTURAL
SPRAYED FIRE-RESISTANT MATERIAL
STEEL BEAM OR STEEL JOIST. SEE STRUCTURAL "

NOT USED

FIRE RATING & REFERENCE	1 HOUR***	UL (TBD)	SOUND RATING & REFERENCE	EFFECTIVE R VALUE FOR SYSTEM	25.0

R2 LIGHTWEIGHT CONCRETE / METAL DECK (1 HOUR)

LIGHTWEIGHT INSULATING CONCRETE
CONTINUOUS RIGID INSULATION, STEPPED AS REQUIRED TO CREATE ROOF SLOPE
CORRUGATED VENTED METAL DECKING - SEE STRUCTURAL
SPRAYED FIRE-RESISTANT MATERIAL
STEEL BEAM OR STEEL JOIST. SEE STRUCTURAL "

NOT USED

FIRE RATING & REFERENCE	1 HOUR***	UL (TBD)	SOUND RATING & REFERENCE	EFFECTIVE R VALUE FOR SYSTEM	25.0

R3 PVC MEMBRANE / METAL DECK (NC)

PVC MEMBRANE ROOFING
LIGHTWEIGHT INSULATING CONCRETE
CONTINUOUS RIGID INSULATION, STEPPED AS REQUIRED TO CREATE ROOF SLOPE
CORRUGATED VENTED METAL DECKING - SEE STRUCTURAL
STEEL BEAM OR STEEL JOIST. SEE STRUCTURAL "

FIRE RATING & REFERENCE	NON COMBUSTIBLE		SOUND RATING & REFERENCE	EFFECTIVE R VALUE FOR SYSTEM	25.0

R4 PVC MEMBRANE / TECTUM DECK (NC)

PVC MEMBRANE ROOFING
LIGHTWEIGHT INSULATING CONCRETE
CONTINUOUS RIGID INSULATION, STEPPED AS REQUIRED TO CREATE ROOF SLOPE
CEMENTITIOUS WOOD-FIBER DECK
STEEL BEAM OR STEEL JOIST. SEE STRUCTURAL "

NOT USED

FIRE RATING & REFERENCE	NON COMBUSTIBLE		SOUND RATING & REFERENCE	EFFECTIVE R VALUE FOR SYSTEM	25.0

R5 LIGHTWEIGHT CONCRETE / TECTUM DECK (NC)

LIGHTWEIGHT INSULATING CONCRETE, STEPPED AS REQUIRED TO CREATE ROOF SLOPE
CONTINUOUS RIGID INSULATION, STEPPED AS REQUIRED TO CREATE ROOF SLOPE
CEMENTITIOUS WOOD-FIBER DECK
STEEL BEAM OR STEEL JOIST. SEE STRUCTURAL "

NOT USED

FIRE RATING & REFERENCE	NON COMBUSTIBLE		SOUND RATING & REFERENCE	EFFECTIVE R VALUE FOR SYSTEM	25.0

R6 METAL ROOF / METAL FRAMING (NC)

PRE-FINISHED PRE-FORMED STANDING SEAM METAL ROOF PANELS
ROOFING UNDERLAYMENT, HIGH TEMPERATURE (ICE & WATER SHIELD)
1-1/2" CONTINUOUS RIGID INSULATION
VAPOR BARRIER
CORRUGATED METAL DECKING - SEE STRUCTURAL
PRE-ENGINEERED METAL ROOF TRUSS. SEE STRUCTURAL

FIRE RATING & REFERENCE	NON COMBUSTIBLE		SOUND RATING & REFERENCE	EFFECTIVE R VALUE FOR SYSTEM	-

R8 PVC MEMBRANE / METAL DECK (1 HOUR)

PVC MEMBRANE ROOFING
COVER BOARD
CONTINUOUS RIGID INSULATION, STEPPED AS REQUIRED TO CREATE ROOF SLOPE
CORRUGATED VENTED METAL DECKING - SEE STRUCTURAL
SPRAYED FIRE-RESISTANT MATERIAL
STEEL BEAM OR STEEL JOIST. SEE STRUCTURAL

NOT USED

FIRE RATING & REFERENCE	1 HOUR***	UL (TBD)	SOUND RATING & REFERENCE	EFFECTIVE R VALUE FOR SYSTEM	25.0

GENERAL NOTES

A. THE CONSTRUCTION SUBSYSTEMS AND PARTITION TYPES SHOWN INDICATE THE GENERAL CONSTRUCTION FEATURES OF THE MAJORITY OF THE CONSTRUCTION SYSTEMS TO BE PROVIDED. THEY ARE NOT INTENDED TO REPRESENT A COMPLETE LISTING OF SYSTEMS REQUIRED AND DO NOT NECESSARILY INDICATE ALL OF THE CONSTRUCTION REQUIREMENTS TO BE PROVIDED BY THE CONTRACT DOCUMENTS.
B. SEE REFLECTED CEILING PLANS FOR ADDITIONAL REQUIREMENTS FOR PARTITION TYPES.
C. REFERENCE FOR FIRE RESISTANCE & SOUND RATINGS:
- CCMA: CAROLINAS CONCRETE MASONRY ASSOCIATION, CONCRETE MASONRY HANDBOOK, SOUND CONTROL
- GA: GYPSUM ASSOCIATION, FIRE RESISTANCE DESIGN MANUAL, 11TH EDITION
- NCMA: NATIONAL CONCRETE MASONRY ASSOCIATION, TEK NOTES
- SA: SHINER AND ASSOCIATES
- SBCC: STANDARD BUILDING CODE CONGRESS, LATEST EDITION
- UL: UNDERWRITERS LABORATORY, INC., FIRE RESISTANCE DIRECTORY

D. WHERE FURRED/SINGLE FACED SYSTEMS OCCUR ON CONCRETE MASONRY UNIT WALL OR PARTITION SURFACE, PROVIDE GYPSUM BOARD TO 4" ABOVE CEILING, OR IF NO CEILING OCCURS, PROVIDE GYPSUM BOARD TO UNDERSIDE OF DECK.

NOTES

1. CONCRETE MASONRY UNIT WALLS AND PARTITIONS: PROVIDE HORIZONTAL JOINT REINFORCEMENT, VERTICAL REINFORCEMENT, BOND BEAMS, GROUTING, AND ADDITIONAL REQUIREMENTS AS INDICATED BY STRUCTURAL DRAWINGS AND SPECIFICATIONS.
2. COLOR, TEXTURE AND FACE PATTERN MAY VARY. SEE MISCELLANEOUS AND EXTERIOR COLOR SCHEDULE (SPEC SECT 9000), SPECIFICATIONS AND DRAWINGS FOR CLARIFICATION.
3. KEEP CAVITY CLEAR OF ALL MORTAR.
4. SEE FINISH SCHEDULE FOR LOCATION OF APPLIED FINISHES (SUCH AS CERAMIC TILE, WALL COVERING, ETC) THAT MAY AFFECT THE PARTITION SURFACE AND CONSTRUCTION REQUIREMENTS.
5. WHERE CERAMIC TILE AND CEMENTITIOUS BACKER UNIT ARE NOT SCHEDULED TO BE FULL HEIGHT OF PARTITION, PROVIDE GYPSUM BOARD (TYPE X @ RATED PARTITIONS) @ THOSE PORTIONS OF THE PARTITION NOT SCHEDULED TO RECEIVE CERAMIC TILE. CEMENTITIOUS BACKER UNIT TO BE SAME THICKNESS AS GYPSUM BOARD.
6. PROVIDE FIRE RATED CMU (OR EQUIVALENT) WHERE PARTITION INDICATED TO BE FIRE RATED ON REFLECTED CEILING PLANS. RATED PARTITION TO MEET CONSTRUCTION REQUIREMENTS OF FIRE RATING REFERENCE LISTED.
7. PROVIDE MANUFACTURER'S PROPRIETARY TYPE 'X' GYPSUM BOARD (MEETING THE DESIGNATED FIRE REFERENCE LISTED) WHERE PARTITION IS INDICATED TO BE FIRE RATED ON REFLECTED CEILING PLANS. RATED PARTITION TO MEET CONSTRUCTION REQUIREMENTS OF FIRE RATING REFERENCE LISTED.
8. PROVIDE ACOUSTICAL SEALANT (09250.K) AT PERIMETER OF ALL SOUND RATED PARTITIONS AND AT ALL PARTITION PENETRATIONS. IF PARTITION IS FIRE RATED, PROVIDE UL LABELED FIRESTOPPING IN PLACE OF ACOUSTICAL SEALANT. AT PARTITIONS THAT ARE SOUND AND FIRE RATED, PROVIDE ACOUSTICAL SEALANT AT PARTITION PENETRATIONS THAT DO NOT REQUIRE FIRESTOPPING (EXAMPLE: DUCT PENETRATIONS WITH FIRE DAMPERS).

SAVANNAH-CHATHAM COUNTY PUBLIC SCHOOL SYSTEM

SCCPSS

RFP C24-01 GROVES ATHLETIC FIELDS & FIELDHOUSE

LS3P

321 WEST CONGRESS STREET SUITE 301
SAVANNAH, GEORGIA 31401
TEL. 912.695.2111 FAX 912.298.0206
WWW.LS3P.COM

STATE OF GEORGIA
APRIL W. MUNDY
5/12/2023
CERTIFICATE NO. 013502
REGISTERED ARCHITECT

MEMBERS OF THE AMERICAN INSTITUTE OF ARCHITECTS

COPYRIGHT 2019 ALL RIGHTS RESERVED
PRINTED OR ELECTRONIC DRAWINGS AND DOCUMENTATION MAY NOT BE REPRODUCED IN ANY FORM WITHOUT WRITTEN PERMISSION FROM LS3P ASSOCIATES LTD.

REVISIONS:

No.	Description	Date
3	Addendum 7	07/21/23

PROJECT: 5201-192070
DATE: 10/09/2020
DRAWN BY: Author
CHECKED BY: AWM

CONSTRUCTION SUBSYSTEMS CONT.

A-005

BID SET

BIM 360://SCCPSS New K-12 Multi-School/ARCH_GrovesK12_K12_v2020.rvt
5/29/2023 10:26:26 AM

B1 FIRST FLOOR PLAN
1/8" = 1'-0"

PARTITION LEGEND

1. ALL EXTERIOR WALLS TO BE TYPE **W1** U.N.O.
2. ALL INTERIOR MASONRY PARTITIONS TO BE TYPE **8M** U.N.O.
3. ALL INTERIOR METAL STUD PARTITIONS TO BE TYPE **3AS** U.N.O.

- NON-RATED PARTITION
- 1 HR. RATED PARTITION TO DECK
- 2 HR. RATED PARTITION TO DECK
- SMOKE RATED PARTITION TO DECK

NOTE: SEE SHEET A-004 AND A-005 FOR CONSTRUCTION SUBSYSTEMS.
SEE SHEET A-006 FOR CONSTRUCTION OF PARTITION TYPES.

FLOOR PLAN GENERAL NOTES

A. EXTERIOR DIMENSIONS AT MASONRY VENEER ARE TO FACE OF MASONRY.
B. EXTERIOR DIMENSION AT PRECAST ARE TO FACE OF PRECAST.
C. INTERIOR DIMENSIONS INDICATED ARE TO FACE OF STUD AND CENTERLINES OF COLUMNS, U.N.O. DIMENSIONS TO FURRED OUT CMU WALLS ARE TO FACE OF CMU.
D. ALL CMU WALLS ON SECOND FLOOR TO RECEIVE FURRING TYPE 0F, EXCEPTING ARMORY, VAULT, STAIRWELL INTERIORS, AND MECHANICAL/STORAGE ROOMS.
E. LOCATE ALL DOOR OPENINGS IN CMU WALLS 8" FROM NEAREST PERPENDICULAR WALL, U.N.O.
F. LOCATE ALL DOOR OPENINGS IN STUD WALLS 4" FROM NEAREST PERPENDICULAR WALL, U.N.O.
G. FIRE AND SOUND RATED WALLS/PARTITIONS TO BE CONSTRUCTED TIGHT TO STRUCTURE, PIPING, DUCTWORK AND OTHER PENETRATIONS. ALL WORK IS TO BE BRACED TO STRUCTURE ABOVE.
H. WHERE PARTITIONS OF DIFFERENT FIRE RATINGS INTERSECT, THE HIGHEST RATED PARTITION SHALL CONTINUE THROUGH. MAINTAIN PARTITION FIRE RATING BEHIND RECESSED FIRE EXTINGUISHER CABINETS.
I. INSTALL BLOCKING IN PARTITIONS FOR CASEWORK, WALL MOUNTED EQUIPMENT, TRIM AND RELATED CONSTRUCTION AS INDICATED IN THE SPECIFICATIONS.
J. SEE LIFE SAFETY PLANS FOR REQUIRED FIRE SEPARATION WALLS.
K. SEE SHEETS A-600-610 FOR DOOR, LOUVER, WINDOW, & GLAZING TYPES.
L. SEE SHEETS A-770-771 FOR CASEWORK AND EQUIPMENT SCHEDULES, DESIGNATIONS & DETAILS.
M. SEE SHEETS A-701-703 FOR FINISH FLOORING, TRANSITIONS, PATTERNS AND WALL PROTECTION.
N. SEE SHEET A-700 FOR FINISH SCHEDULE.
O. SEE SHEETS A-401-421 FOR ENLARGED PLANS AND ELEVATIONS INDICATING ADDITIONAL DIMENSIONS AND PARTITION TYPES, AND ACCESSORY DESCRIPTIONS & MOUNTING HEIGHTS.
P. SEE STRUCTURAL DRAWINGS FOR SLAB DEPRESSIONS AND CUTOUTS.
Q. SEE BUILDING ELEVATION DRAWINGS FOR LOCATION OF EXTERIOR MASONRY CONTROL JOINTS.

KEY PLAN

SAVANNAH-CHATHAM COUNTY PUBLIC SCHOOL SYSTEM

SCCPSS

RFP C24-01 GROVES ATHLETIC FIELDS & FIELDHOUSE

LS3P
321 WEST CONGRESS STREET SUITE 301
SAVANNAH, GEORGIA 31401
TEL. 912.695.2111 FAX 912.298.0206
WWW.LS3P.COM

STATE OF GEORGIA
APRIL W. MUNDY
5/12/2023
CERTIFICATE NO. 013910
REGISTERED ARCHITECT

MEMBERS OF THE AMERICAN INSTITUTE OF ARCHITECTS

COPYRIGHT 2019 ALL RIGHTS RESERVED
PRINTED OR ELECTRONIC DRAWINGS AND DOCUMENTATION MAY NOT BE REPRODUCED IN ANY FORM WITHOUT WRITTEN PERMISSION FROM LS3P ASSOCIATES LTD.

REVISIONS:

No.	Description	Date
1	Addendum 5	07/12/23
2	Addendum 6	07/20/23
3	Addendum 7	07/21/23

PROJECT: 5201-192070
DATE: 07/12/2023
DRAWN BY: WJC
CHECKED BY: AWM

1ST FLOOR PLAN - FIELDHOUSE

A-101

BID SET

BIM 360://5201-192070 SCCPSS NEW K-12 ATHLETICS\ARCH_GrovesK12_Fieldhouse_NEW.rvt
7/21/2023 1:01:10 PM

DOOR AND FRAME SCHEDULE

DOOR NUMBER	ROOM	PANEL TYPE/MATERIAL	PANEL FINISH	PANEL WIDTH	PANEL HEIGHT	PANEL THICKNESS	FRAME TYPE/MATERIAL	FRAME FINISH	FRAME HEAD HEIGHT	HW SET	HEAD	JAMB	LABEL	REMARKS
101	WOMEN	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	077	B5 / A-608	A5 / A-608	-	3
102	MEN	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	077	B5 / A-608	A5 / A-608	-	3
103	CONCESSIONS	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	038	B5 / A-608	A5 / A-608	-	3
104	JAN	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	038	B5 / A-608	A5 / A-608	-	3
105	ELEC	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	038	B5 / A-608	A5 / A-608	-	3
106	WOMEN	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	077	B5 / A-608	A5 / A-608	-	3
107	MEN	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	077	B5 / A-608	A5 / A-608	-	3
108	CONCESSIONS	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	038	B5 / A-608	A5 / A-608	-	3
109	JAN	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	038	B5 / A-608	A5 / A-608	-	3
110	ELEC	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	038	B5 / A-608	A5 / A-608	-	3
1100.S	STAIR 1	PNL-N-HM	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	142	B4 / A-608	A4 / A-608	60	5
1101.1	VEST	PNL-F-HM	PTD	3'-6"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	142	B5 / A-608	A5 / A-608	-	
1101.3	VISITOR LOCKER	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	142	B5 / A-608	A5 / A-608	-	
1102.1	TOILET	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	073	B5 / A-608	A5 / A-608	-	
1102.2	VISITOR SHOWER	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	055	B2 / A-608	A2 / A-608	-	
1102.3	TOILET	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	073	B5 / A-608	A5 / A-608	-	
1102.4	TOILET	PNL-F-WD	STD	2'-0"	5'-8"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	163	E3 / A-540	D2 / A-540	-	
1102.5	TOILET	PNL-F-WD	STD	2'-0"	5'-8"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	163	E3 / A-540	D2 / A-540	-	
1102.6	TOILET	PNL-F-WD	STD	2'-0"	5'-8"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	163	E3 / A-540	D2 / A-540	-	
1102.7	TOILET	PNL-F-WD	STD	2'-0"	5'-8"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	163	E3 / A-540	D2 / A-540	-	
1102.8	TOILET	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	163	B5 / A-608	A5 / A-608	-	
1103.1	VEST	PNL-F-HM	PTD	3'-6"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	142	B5 / A-608	A5 / A-608	-	
1103.2	GROVES FB LOCKER	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	142	B5 / A-608	A5 / A-608	-	
1200.1	CORRIDOR	PNL-FGX-AL	PFM	6'-0"	7'-0"	0'-1 3/4"	FRM-00AL(CW)	PFM	0'-0"	093	B1 / A-609	C1 / A-609	-	3, 5, 10
1200.2	CORRIDOR	PNL-FGX-AL	PFM	6'-0"	7'-0"	0'-1 3/4"	FRM-00AL(CW)	PFM	0'-0"	093	B1 / A-609	C1 / A-609	-	3, 5, 10
1200.3	CORRIDOR	PNL-FG-AL		3'-0"	7'-0"	0'-1 3/4"	FRM-01AL(CW)		0'-2"	98.1				
1200.S	STAIR 2	PNL-F-WD	PFM	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	129	B1 / A-608	A1 / A-608	60	
1201.1	VEST	PNL-F-HM	PTD	3'-6"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	141	B5 / A-608	A5 / A-608	-	
1201.2	VEST	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	142	B5 / A-608	A5 / A-608	-	
1201.3	HOME TEAM	PNL-NP		4'-0"	7'-4"	0'-0"	FRM-NF		0'-0"					
1201.4	VEST	PNL-NP		4'-0"	7'-4"	0'-0"	FRM-NF		0'-0"					
1202.1	VEST	PNL-F-HM	STD	3'-6"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	142	B5 / A-608	A5 / A-608	-	
1202.2	ATHLETIC TRAINING	PNL-F-WD	PFM	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	001	B1 / A-608	A1 / A-608	-	
1202.3	ATHLETIC TRAINING	PNL-F-HM	PFM	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	001	B5 / A-608	A5 / A-608	-	
1203.1	HOME SHOWER	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	059	B5 / A-608	A5 / A-608	-	
1203.2	HOME TOILET	PNL-F-WD	STD	2'-7"	5'-8"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	163	E3 / A-540	D2 / A-540	-	
1203.3	HOME TOILET	PNL-F-WD	STD	2'-0"	5'-8"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	163	E3 / A-540	D2 / A-540	-	
1203.4	HOME TOILET	PNL-F-WD	STD	2'-0"	5'-8"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	163	E3 / A-540	D2 / A-540	-	
1203.5	HOME TOILET	PNL-F-WD	STD	2'-0"	5'-8"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	163	E3 / A-540	D2 / A-540	-	
1203.6	HOME TOILET	PNL-F-WD	STD	2'-0"	5'-8"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	163	E3 / A-540	D2 / A-540	-	
1204.1	JAN. & LAUNDRY	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	013	B1 / A-608	A1 / A-608	-	
1204.2	TEAM STORAGE	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	136	B5 / A-608	A5 / A-608	-	
1205	WOMEN	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	056	B1 / A-608	A1 / A-608	-	
1206	MEN	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	056	B1 / A-608	A1 / A-608	-	
1207	ADMIN.	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	001	B1 / A-608	A1 / A-608	-	
1208.1	TEAM STORAGE	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-10HM1	PTD	0'-2"	136	C5 / A-608	C4 / A-608	-	1, 2, 3, 5
1208.2	TEAM STORAGE	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	136	B5 / A-608	A5 / A-608	-	
1209	VISITOR TICKETS	PNL-N-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	037	B5 / A-608	A5 / A-608	-	3, 10
1210	ELEC	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-10HM1	PTD	0'-2"	136	C5 / A-608	C4 / A-608	-	1, 2, 3, 5
1211	DATA	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	012	B5 / A-608	A5 / A-608	-	
1212	STORAGE	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-10HM1	PTD	0'-2"	136	C5 / A-608	C4 / A-608	-	1, 2, 3, 5
1213	RISER	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-10HM1	PTD	0'-2"	136	C5 / A-608	C4 / A-608	-	1, 2, 3, 5
1214	TICKETS HOME	PNL-N-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	037	B5 / A-608	A5 / A-608	-	3, 10
1215	SRO	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	037	B5 / A-608	A5 / A-608	-	3, 5
1300.S1	STAIR 3	PNL-F-HM	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	112.1	B1 / A-608	A1 / A-608	60	
1300.S2	STAIR 3	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-10HM1	PTD	0'-2"	130.1	C5 / A-608	C4 / A-608	60	
1301.1	FIELD ATHLETIC STORAGE	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-10HM1	PTD	0'-2"	136	C5 / A-608	C4 / A-608	-	1, 2, 3, 5
1301.2	FIELD ATHLETIC STORAGE	PNL-F2-STL	PTD	10'-0"	9'-4"	0'-2"	FRM-60STL	PTD	0'-2"	159	D1 / A-609	C3 / A-608	-	8
1302.1	K9 UNIT	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-10HM1	PTD	0'-2"	038	C5 / A-608	C4 / A-608	-	
1302.2	K9 UNIT	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	013	B2 / A-608	A2 / A-608	-	
1302.3	K9 UNIT	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	001	B2 / A-608	A2 / A-608	-	
1303.1	TOILET	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	056	B2 / A-608	A2 / A-608	90	
1303.2	TOILET	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	056	B2 / A-608	A2 / A-608	-	
1304.1	FIELD MAINT. EQUIP	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-10HM1	PTD	0'-2"	136	C5 / A-608	C4 / A-608	-	1, 2, 3, 5

DOOR AND FRAME SCHEDULE

DOOR NUMBER	ROOM	PANEL TYPE/MATERIAL	PANEL FINISH	PANEL WIDTH	PANEL HEIGHT	PANEL THICKNESS	FRAME TYPE/MATERIAL	FRAME FINISH	FRAME HEAD HEIGHT	HW SET	HEAD	JAMB	LABEL	REMARKS
1304.2	FIELD MAINT. EQUIP	PNL-F2-STL	PFM	10'-0"	9'-4"	0'-2"	FRM-60STL	PTD	0'-2"	159	D1 / A-609	C3 / A-608	-	8
1304.3	FIELD MAINT. EQUIP	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	111	B2 / A-608	A2 / A-608	-	
1305.1	DISTRICT ATHLETIC STORAGE	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-10HM1	PTD	0'-2"	136	C5 / A-608	C4 / A-608	-	1, 2, 3, 5
1305.2	DISTRICT ATHLETIC STORAGE	PNL-F2-STL	PTD	10'-0"	9'-4"	0'-2"	FRM-60STL	PTD	0'-2"	159	D1 / A-609	C3 / A-608	-	8
1305.3	DISTRICT ATHLETIC STORAGE	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	011	B2 / A-608	A2 / A-608	-	
1306	ELEC	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-10HM1	PTD	0'-2"	136	C5 / A-608	C4 / A-608	-	1, 2, 3, 5
1306.1	EM. ELEC	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	136	B2 / A-608	A2 / A-608	90	
2100	CORRIDOR	PNL-FG-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	106	B1 / A-608	A1 / A-608	-	
2100.S	STAIR 1	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	126	B1 / A-608	A1 / A-608	60	
2101.1	EXEC. ADMIN	PNL-FG-AL	PFM	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PFM	0'-2"	040	B1 / A-608	A1 / A-608	-	
2101.2	EXEC. ADMIN	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	040	B1 / A-608	A1 / A-608	-	
2101.3	TOILET	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	040	B1 / A-608	A1 / A-608	-	
2101.4	CHIEF	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	106	B1 / A-608	A1 / A-608	-	
2102.1	CONFERENCE	PNL-FG-AL	PFM	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PFM	0'-2"	040	B1 / A-608	A1 / A-608	-	
2102.2	CONFERENCE	PNL-FG-AL	PFM	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PFM	0'-2"	040	B1 / A-608	A1 / A-608	-	
2103	DC	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	040	B1 / A-608	A1 / A-608	-	
2104	OPEN OFFICE	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	040	B1 / A-608	A1 / A-608	-	
2105	DC	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	040	B1 / A-608	A1 / A-608	-	
2106	OPEN OFFICE	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	040	B1 / A-608	A1 / A-608	-	
2107	LOUNGE	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	040	B1 / A-608	A1 / A-608	-	
2108	MEN	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	056	B1 / A-608	A1 / A-608	-	
2109	WOMEN	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	056	B1 / A-608	A1 / A-608	-	
2110.1	RECORDS	PNL-FG-AL	PFM	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PFM	0'-2"	040	B1 / A-608	A1 / A-608	-	
2110.2	RECORDS	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	011	B1 / A-608	A1 / A-608	-	
2111	STORAGE	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	011	B1 / A-608	A1 / A-608	-	
2200.1	CORRIDOR	PNL-FG-AL	PFM	3'-0"	7'-0"	0'-1 3/4"	FRM-00AL(CW)	PFM	0'-0"	098.1				10
2200.S	STAIR 2	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	126	B1 / A-608	A1 / A-608	60	
2202	ADMIN	PNL-FG-AL	PFM	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PFM	0'-2"	003	B1 / A-608	A1 / A-608	-	
2203	ELEC	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	012	B1 / A-608	A1 / A-608	-	
2205	DATA	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	012	B1 / A-608	A1 / A-608	-	
2206	WORKROOM	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	047	B1 / A-608	A1 / A-608	-	
2207	OFFICE	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	040	B1 / A-608	A1 / A-608	-	
2207.1	CLOSET	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	011	B1 / A-608	A1 / A-608	-	
2208	ADMIN SGT/CERT.	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	040	B1 / A-608	A1 / A-608	-	
2208.1	CLOSET	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	011	B1 / A-608	A1 / A-608	-	
2209.1	COMMAND CENTER	PNL-FG-AL	PFM	3'-0"	7'-0"	0'-1 3/4"	FRM-00AL(CW)	PFM	0'-0"	085				
2209.2	COMMAND CENTER STO.	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	011	B1 / A-608	A1 / A-608	-	
2209.3	COMMAND CENTER	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	005	B1 / A-608	A1 / A-608	-	
2210	PM	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	001	B1 / A-608	A1 / A-608	-	
2211	EMERGENCY LT	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	001	B1 / A-608	A1 / A-608	-	
2212	TOILET	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	055	B1 / A-608	A1 / A-608	-	
2213.1	MULTI-PURPOSE ROOM	PNL-FGX-AL	PFM	6'-4"	7'-0"	0'-1 3/4"	FRM-00AL1	PFM	0'-2"	089	C5 / A-608	C4 / A-608	-	
2213.2	MULTI-PURPOSE ROOM	PNL-FGX-AL	PFM	6'-4"	7'-0"	0'-1 3/4"	FRM-00AL1	PFM	0'-2"	089	C5 / A-608	C4 / A-608	-	
2213.3	MULTI-PURPOSE ROOM	PNL-FGX-AL	PFM	6'-0"	7'-0"	0'-1 3/4"	FRM-00AL(CW)	PFM	0'-0"	079	B1 / A-609	C1 / A-609	-	
2213.4	MULTI-PURPOSE ROOM	PNL-FGX-AL	PFM	6'-0"	7'-0"	0'-1 3/4"	FRM-00AL(CW)	PFM	0'-0"	079	B1 / A-609	C1 / A-609	-	
2213.5	MULTI-PURPOSE ROOM	PNL-FGX-AL	PFM	6'-0"	7'-0"	0'-1 3/4"	FRM-00AL(CW)	PFM	0'-0"	079	B1 / A-609	C1 / A-609	-	
2213.7	STORAGE	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	011	B1 / A-608	A1 / A-608	-	
2214.1	BREAK	PNL-FG-AL	PFM	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PFM	0'-2"	070	B1 / A-608	A1 / A-608	-	
2214.2	BREAK	PNL-FG-AL	PFM	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PFM	0'-2"	070	B1 / A-608	A1 / A-608	-	
2215	OL	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	040	B1 / A-608	A1 / A-608	-	
2216	CIU/IU	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	040	B1 / A-608	A1 / A-608	-	
2217	STORAGE	PNL-FGX-AL	STD	6'-4"	7'-0"	0'-1 3/4"	FRM-00AL1	PTD	0'-2"	033	C5 / A-608	C4 / A-608	-	
2218	CONFERENCE	PNL-FG-AL	PFM	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PFM	0'-2"	040	B1 / A-608	A1 / A-608	-	
2219	CORRIDOR	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	069	B1 / A-608	A1 / A-608	-	
2219.1	SHOWER	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	058	B1 / A-608	A1 / A-608	-	
2220	JAN	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	011	B1 / A-608	A1 / A-608	-	
2221	WOMEN	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	069	B1 / A-608	A1 / A-608	-	
2221.1	WOMEN	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	058	B1 / A-608	A1 / A-608	-	
2249	VEST	PNL-NP		3'-6"	7'-0"	0'-1 3/4"	FRM-NF		0'-0"					
2300.S	STAIR 3	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	126	B4 / A-608	A4 / A-608	60	1, 2, 5
2301.1	EVIDENCE STOR.	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	106	B1 / A-608	A1 / A-608	-	
2301.2	CHECK IN	PNL-F-HM	PTD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	106	B1 / A-608	A1 / A-608	-	
2301.3	DRUGS	PNL-F-WD	STD	2'-6"	5'-8"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	013	E3 / A-540	D2 / A-540	-	
2302.1	QUARTER MASTER OFFICE	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	047	B4 / A-608	A4 / A-608	60	
2302.2	QM STOR.	PNL-F-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-4"	012	B4 / A-608	A4 / A-608	60	
2303	SFL	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	040	B1 / A-608	A1 / A-608	-	
2304	SFL	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	040	B1 / A-608	A1 / A-608	-	
2305	OL	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	040	B1 / A-608	A1 / A-608	-	
2306	CUSTODIAN	PNL-N-WD	STD	3'-0"	7'-0"	0'-1 3/4"	FRM-00HM1	PTD	0'-2"	040	B1 / A-608	A1 / A-608	-	

F1 FRM-00HM1 3/8" = 1'-0"
F2 FRM-00HM2 3/8" = 1'-0"
F3 FRM-10HM1 3/8" = 1'-0"
F4 FRM-60STL 3/8" = 1'-0"

P1 PNL-F-WD 3/8" = 1'-0"
P2 PNL-F-HM 3/8" = 1'-0"
P3 PNL-FG-AL 3/8" = 1'-0"
P4 PNL-FGX-AL 3/8" = 1'-0"
P5 PNL-N-WD 3/8" = 1'-0"
P6 PNL-G-WD 3/8" = 1'-0"
P7 PNL-F2-STL 3/8" = 1'-0"

DOOR REMARK NOTES

1. ACCESS CONTROL
2. CARD READER
3. DOOR POSITION SWITCH
4. MAG LOCK HOLD OPEN
5. PANIC DEVICE
6. ALLOW FOR DOOR SWING GREATER THAN 90 DEG, SEE PLANS.
7. PROVIDE HIGH STC/ACOUSTICAL DOOR HARDWARE
8. COILING DOOR
9. EXIT ALARM; DOOR FOR EMERGENCY EGRESS ONLY. PROVIDE SIGNAGE.
10. LAMINATED TEMPERED GLASS
11. AI PHONE
12. SMOKE CONTROL DOORS
13. ACTIVE AND INACTIVE LEAF

* SEE DOOR SCHEDULE AND HARDWARE SETS FOR ADDITIONAL DOOR AND ACCESS CONTROL INFORMATION.

GENERAL DOOR NOTES

A. SEE FLOOR PLANS AND ELEVATIONS FOR DOOR AND FRAME LOCATIONS.
B. OVERALL HORIZONTAL AND VERTICAL FRAME DIMENSIONS ARE TO MASONRY OPENINGS.
C. VIEW LITES IN ALL NON-LABELED DOORS SHALL BE TEMPERED CLEAR GLASS, UNO.
D. VIEW LITES IN ALL FIRE RATED DOORS SHALL BE FIRE RATED GLASS, UNO.
E. SEE FRAME ELEVATION FOR SILL HEIGHTS AFF.
F. CENTERLINES OF ALL EXIT DEVICES SHALL BE 37", UNO.
G. CENTER HOLLOW METAL FRAMES IN CMU WALLS, UNO.
H. COORDINATE EXIT HARDWARE MOUNTING HEIGHT SO THAT IT DOES NOT CONFLICT WITH VISION LITES.
I. PROVIDE 6" STILE ON WOOD AND HOLLOW METAL DOORS. PROVIDE 5" STILE ON ALUMINUM DOORS, UNO.
J. DOOR CLOSERS SHALL BE ADJUSTED TO ALLOW DOORS TO OPEN TO 110 DEGREES.
K. SMOKE TIGHT DOORS SHALL NOT HAVE AIR TRANSFER OPENINGS AND SHALL NOT HAVE AN UNDERCUT IN EXCESS OF THE CLEARANCE PERMITTED IN ACCORDANCE WITH NFPA 80.
L. ALL INTERIOR HOLLOW METAL AND WOOD DOORS SHALL RECEIVE HOLLOW METAL FRAMES. FRAMES IN GYPSUM BOARD SHALL HAVE 2" HEADS, AND MASONRY PARTITIONS SHALL HAVE 4" HEADS, UNO.
M. ALL EXTERIOR DOORS TO RECEIVE CONTACTS.
N. REFER TO DETAIL 5/T-301 FOR WIRING AND PATHWAY REQUIREMENTS FOR ALL ELECTRIFIED FRAMES/DOORS REGARDLESS OF BEING NOTED ON E-SHEETS AND T-SHEETS.

SAVANNAH-CHATHAM COUNTY PUBLIC SCHOOL SYSTEM

SCCPSS

RFP C24-01 GROVES ATHLETIC FIELDS & FIELDHOUSE

LS3P
321 WEST CONGRESS STREET SUITE 301
SAVANNAH, GEORGIA 31401
TEL. 912.695.2111 FAX 912.298.0206
WWW.LS3P.COM

STATE OF GEORGIA
APRIL W. MUNDY
CERTIFICATE NO. 013902
5/12/2023
REGISTERED ARCHITECT

MEMBERS OF THE AMERICAN INSTITUTE OF ARCHITECTS

COPYRIGHT 2019 ALL RIGHTS RESERVED PRINTED OR ELECTRONIC DRAWINGS AND DOCUMENTATION MAY NOT BE REPRODUCED IN ANY FORM WITHOUT WRITTEN PERMISSION FROM LS3P ASSOCIATES LTD.

REVISIONS:

No.	Description	Date
3	Addendum 7	07/21/23

PROJECT: 5201-192070
DATE: 07/12/2023
DRAWN BY: KAS
CHECKED BY: AWM

DOOR SCHEDULE, DOOR & FRAME TYPE LEGEND

A-600

BID SET

C1 1ST FLOOR - HARDWARE COORDINATION PLAN
1/8" = 1'-0"

A1 1ST FLOOR RESTROOMS/CONCESSIONS - AWAY
1/8" = 1'-0"

A3 1ST FLOOR RESTROOMS/CONCESSIONS - HOME
1/8" = 1'-0"

ACCESS CONTROL PLAN LEGEND

AC	ACCESS CONTROL
DPS	DOOR POSITION SWITCH
CR	CARD READER
HO	HOLD OPEN
EA	EXIT ALARM
PD	PANIC DEVICE
REX	REQUEST TO EXIT

* SEE DOOR SCHEDULE AND HARDWARE SETS FOR ADDITIONAL DOOR AND ACCESS CONTROL INFORMATION.

REFER TO E-SHEETS AND T-SHEETS FOR COORDINATION OF PATHWAY.

SECURITY DOOR HARDWARE LEGEND (NORMAL OPERATING HOURS)

EXTERIOR ACCESS
EXTERIOR ALWAYS LOCKED UNLESS ELECTRONICALLY RELEASED (SEE SET)
INTERIOR ALWAYS FREE EGRESS
ACCESS CONTROL AND CARD READER (MONITORED)

EXTERIOR ACCESS
EXTERIOR ALWAYS LOCKED UNLESS ELECTRONICALLY RELEASED (SEE SET)
INTERIOR ALWAYS FREE EGRESS
CARD READER, ACCESS CONTROL, AND AI

INTERIOR SECURE ACCESS
INGRESS ALWAYS LOCKED UNLESS ELECTRONICALLY RELEASED (SEE SET)
ACCESS CONTROL AND CARD READER (MONITORED; DPS & REX)

DUAL AUTHENTICATION ACCESS
INGRESS ALWAYS LOCKED UNLESS ELECTRONICALLY RELEASED BY DUAL AUTHENTICATION PROCESS (SEE SET)
ACCESS CONTROL AND CARD READER (MONITORED; DPS & REX)

SAVANNAH-CHATHAM COUNTY PUBLIC SCHOOL SYSTEM

SCCPSS

RFP C24-01 GROVES ATHLETIC FIELDS & FIELDHOUSE

LS3P
321 WEST CONGRESS STREET SUITE 301
SAVANNAH, GEORGIA 31401
TEL. 912.695.2111 FAX 912.298.0206
WWW.LS3P.COM

STATE OF GEORGIA
APRIL W. MUNDY
5/12/2023
CERTIFICATE NO. 013599
REGISTERED ARCHITECT

MEMBERS OF THE AMERICAN INSTITUTE OF ARCHITECTS

COPYRIGHT 2019 ALL RIGHTS RESERVED
PRINTED OR ELECTRONIC DRAWINGS AND DOCUMENTATION MAY NOT BE REPRODUCED IN ANY FORM WITHOUT WRITTEN PERMISSION FROM LS3P ASSOCIATES LTD.

REVISIONS:

No.	Description	Date
3	Addendum 7	07/21/23

PROJECT: 5201-192070
DATE: 07/12/2023
DRAWN BY: CA
CHECKED BY: AWM

DOOR & SECURITY HARDWARE PLAN - 1ST FLOOR

A-611

BID SET

BIM 360://5201-192070 SCCPSS NEW K-12 ATHLETICS/ARCH_GrovesK12_Fieldhouse_NEW.rvt
7/21/2023 2:16:09 PM

C1 2ND FLOOR - HARDWARE COORDINATION PLAN
1/8" = 1'-0"

ACCESS CONTROL PLAN LEGEND

AC	ACCESS CONTROL
DPS	DOOR POSITION SWITCH
CR	CARD READER
HO	HOLD OPEN
EA	EXIT ALARM
PD	PANIC DEVICE
REX	REQUEST TO EXIT

3

* SEE DOOR SCHEDULE AND HARDWARE SETS FOR ADDITIONAL DOOR AND ACCESS CONTROL INFORMATION.

REFER TO E-SHEETS AND T-SHEETS FOR COORDINATION OF PATHWAY.

SECURITY DOOR HARDWARE LEGEND (NORMAL OPERATING HOURS)

3

EXTERIOR ACCESS
EXTERIOR ALWAYS LOCKED UNLESS ELECTRONICALLY RELEASED (SEE SET)
INTERIOR ALWAYS FREE EGRESS
ACCESS CONTROL AND CARD READER (MONITORED)

EXTERIOR ACCESS
EXTERIOR ALWAYS LOCKED UNLESS ELECTRONICALLY RELEASED (SEE SET)
INTERIOR ALWAYS FREE EGRESS
CARD READER, ACCESS CONTROL, AND AI

INTERIOR SECURE ACCESS
INGRESS ALWAYS LOCKED UNLESS ELECTRONICALLY RELEASED (SEE SET)
ACCESS CONTROL AND CARD READER (MONITORED; DPS & REX)

DUAL AUTHENTICATION ACCESS
INGRESS ALWAYS LOCKED UNLESS ELECTRONICALLY RELEASED BY DUAL AUTHENTICATION PROCESS (SEE SET)
ACCESS CONTROL AND CARD READER (MONITORED; DPS & REX)

SAVANNAH-CHATHAM COUNTY PUBLIC SCHOOL SYSTEM

SCCPSS

RFP C24-01 GROVES ATHLETIC FIELDS & FIELDHOUSE

LS3P
321 WEST CONGRESS STREET SUITE 301
SAVANNAH, GEORGIA 31401
TEL. 912.695.2111 FAX 912.298.0206
WWW.LS3P.COM

STATE OF GEORGIA
APRIL W. MUNDY
5/12/2023
CERTIFICATE NO. 013593
REGISTERED ARCHITECT

MEMBERS OF THE AMERICAN INSTITUTE OF ARCHITECTS

COPYRIGHT 2019 ALL RIGHTS RESERVED
PRINTED OR ELECTRONIC DRAWINGS AND DOCUMENTATION MAY NOT BE REPRODUCED IN ANY FORM WITHOUT WRITTEN PERMISSION FROM LS3P ASSOCIATES LTD.

REVISIONS:

No.	Description	Date
2	Addendum 6	07/20/23
3	Addendum 7	07/21/23

PROJECT: 5201-192070
DATE: 07/12/2023
DRAWN BY: CA
CHECKED BY: AWM

DOOR & SECURITY HARDWARE PLAN - 2ND FLOOR

A-612

BID SET

BIM 360://5201-192070 SCCPSS NEW K-12 ATHLETICS/ARCH_GrovesK12_Fieldhouse_NEW.rvt
7/21/2023 2:15:17 PM

E1 MASONRY CONTROL JOINT
1 1/2" = 1'-0"

E2 C.M.U. CONTROL JOINT
1 1/2" = 1'-0"

E3 C.M.U. CONTROL JOINT
1 1/2" = 1'-0"

E4 COLUMN @ EXTERIOR WALL
1 1/2" = 1'-0"

E5 CONTROL JOINT
1 1/2" = 1'-0"

E6 COLUMN @ EXTERIOR WALL
1 1/2" = 1'-0"

D1 MASONRY CONTROL JOINT
1 1/2" = 1'-0"

D2 CONTROL JOINT
6" = 1'-0"

D3 HORIZONTAL PIPE RUN
1 1/2" = 1'-0"

D4 PLAN DETAIL
1" = 1'-0"

D5 EXT. MASONRY INTERSECTION
1 1/2" = 1'-0"

D6 MASONRY PARTITION BRACE
1 1/2" = 1'-0"

C1 MTL. STUD/C.M.U. CORNER
1 1/2" = 1'-0"

C2 MTL. STUD/C.M.U. INTERSECTION
1 1/2" = 1'-0"

C3 TYPICAL FLASHING DETAIL
1 : 1

C4 INT. MASONRY INTERSECTION
1 1/2" = 1'-0"

C5 TYPICAL FLASHING DAM
1 1/2" = 1'-0"

C6 WATERPROOFING
1 1/2" = 1'-0"

B1 CONTROL JOINT
1 1/2" = 1'-0"

B2 FLAG POLE DETAIL
1/2" = 1'-0"

B3 MASONRY CONTROL JOINT
1 1/2" = 1'-0"

B4 EXPANSION JOINT
1 1/2" = 1'-0"

A1 EXP. JOINT - C.M.U./GYP. BD.
1 1/2" = 1'-0"

A2 PIPE FLASHING (TYP. VERTICAL)
1 1/2" = 1'-0"

A3 DRINKING FOUNTAIN RECESS
1 1/2" = 1'-0"

NOTE: BULLNOSE DOES NOT APPLY TO CASED OPENING FOR PASS-THRU UNITS @ KITCHEN

A4 BULLNOSE C.M.U.
1 1/2" = 1'-0"

A5 GYP. FURRING @ C.M.U.
1 1/2" = 1'-0"

A6 TOP OF BLOCK PARTITION
1 1/2" = 1'-0"

SAVANNAH-CHATHAM COUNTY PUBLIC SCHOOL SYSTEM

SCCPSS

RFP C24-01
GROVES ATHLETIC FIELDS & FIELDHOUSE

LS3P

321 WEST CONGRESS STREET SUITE 301
SAVANNAH, GEORGIA 31401
TEL. 912.695.2111 FAX 912.298.0206
WWW.LS3P.COM

STATE OF GEORGIA
APRIL W. MUNDY
CERTIFICATE NO. 019867
5/12/2023
REGISTERED ARCHITECT

MEMBERS OF THE AMERICAN INSTITUTE OF ARCHITECTS

COPYRIGHT 2019 ALL RIGHTS RESERVED PRINTED OR ELECTRONIC DRAWINGS AND DOCUMENTATION MAY NOT BE REPRODUCED IN ANY FORM WITHOUT WRITTEN PERMISSION FROM LS3P ASSOCIATES LTD.

REVISIONS:

No.	Description	Date
3	Addendum 7	07/21/23

PROJECT: 5201-192070
DATE: 07/12/2023
DRAWN BY: Author
CHECKED BY: Checker

MISC DETAILS

A-800

BID SET

E1 WAINSCOT - CERAMIC TILE
1 1/2" = 1'-0"

E2 MARBLE THRESHOLD
3" = 1'-0"

E3 CNTRL. JT. @ GYP. BD. CLG.
3" = 1'-0"

E5 STEEL LADDER
1 1/2" = 1'-0"

E6 METAL ACCESS PANEL
1 1/2" = 1'-0"

D1 BRICK STEP FLASHING
1" = 1'-0"

D2 WALKWAY COVER
1 1/2" = 1'-0"

D3 WALKWAY COVER DETAIL
1 1/2" = 1'-0"

C1 HD. - LOUVER @ CMU/BRICK
1 1/2" = 1'-0"

B1 JAMB - LOUVER @ CMU/BRICK
1 1/2" = 1'-0"

B2 LOUVER JAMB @ MTL. PANEL
1 1/2" = 1'-0"

A1 SILL - LOUVER @ CMU/BRICK
1 1/2" = 1'-0"

A2 LOUVER SECTION @ MTL.PANEL
1 1/2" = 1'-0"

A6 DRINKING FOUNTAIN RECESS
1 1/2" = 1'-0"

SAVANNAH-CHATHAM COUNTY PUBLIC SCHOOL SYSTEM

SCCPSS

RFP C24-01 GROVES ATHLETIC FIELDS & FIELDHOUSE

LS3P

321 WEST CONGRESS STREET SUITE 301
SAVANNAH, GEORGIA 31401
TEL. 912.695.2111 FAX 912.298.0206
WWW.LS3P.COM

STATE OF GEORGIA
APRIL W. MUNDY
5/12/2023
CERTIFICATE NO. 013000
REGISTERED ARCHITECT

MEMBERS OF THE AMERICAN INSTITUTE OF ARCHITECTS

COPYRIGHT 2019 ALL RIGHTS RESERVED PRINTED OR ELECTRONIC DRAWINGS AND DOCUMENTATION MAY NOT BE REPRODUCED IN ANY FORM WITHOUT WRITTEN PERMISSION FROM LS3P ASSOCIATES LTD.

REVISIONS:

No.	Description	Date
3	Addendum 7	07/21/23

PROJECT: 5201-192070
DATE: 07/12/2023
DRAWN BY: Author
CHECKED BY: Checker

3

MISC DETAILS

A-801

BID SET

D1 EXPANSION JOINT
1 1/2" = 1'-0"

D2 EXPANSION JOINT
1 1/2" = 1'-0"

D3 EXPANSION JOINT
1 1/2" = 1'-0"

D4 EXPANSION JOINT
1 1/2" = 1'-0"

D5 EXPANSION JOINT
1 1/2" = 1'-0"

C1 EXPANSION JOINT
1 1/2" = 1'-0"

C2 EXPANSION JOINT
1 1/2" = 1'-0"

C3 EXPANSION JOINT
1 1/2" = 1'-0"

C4 EXPANSION JOINT
1 1/2" = 1'-0"

C5 EXPANSION JOINT
1 1/2" = 1'-0"

B1 EXPANSION JOINT
1 1/2" = 1'-0"

B2 EXPANSION JOINT
1 1/2" = 1'-0"

B3 EXPANSION JOINT
1 1/2" = 1'-0"

B4 EXPANSION JOINT
1 1/2" = 1'-0"

B5 EXPANSION JOINT
1 1/2" = 1'-0"

SAVANNAH-CHATHAM COUNTY PUBLIC SCHOOL SYSTEM

SCCPSS

RFP C24-01
GROVES ATHLETIC FIELDS & FIELDHOUSE

LS3P

321 WEST CONGRESS STREET SUITE 301
SAVANNAH, GEORGIA 31401
TEL. 912.695.2111 FAX 912.298.0206
WWW.LS3P.COM

STATE OF GEORGIA
APRIL W. MUNDY
5/12/2023
CERTIFICATE NO. 013002
REGISTERED ARCHITECT

MEMBERS OF THE AMERICAN INSTITUTE OF ARCHITECTS

COPYRIGHT 2019 ALL RIGHTS RESERVED
PRINTED OR ELECTRONIC DRAWINGS AND DOCUMENTATION MAY NOT BE REPRODUCED IN ANY FORM WITHOUT WRITTEN PERMISSION FROM LS3P ASSOCIATES LTD.

REVISIONS:

No.	Description	Date
3	Addendum 7	07/21/23

PROJECT: 5201-192070
DATE: 07/12/2023
DRAWN BY: Author
CHECKED BY: Checker

3

MISC DETAILS

A-802

BID SET

DOOR SCHEDULE

Door Number	Room Name	DOOR Width	DOOR Height	DOOR Material	DOOR Thickness	DOOR Type	FRAME Material	FRAME Sill	FRAME Jamb	FRAME Head	FRAME Type	Hrdwr Set
P01	BOX 1	3'-0"	7'-0"	STEEL	1-3/4"	F	STEEL	7A/SR742	7B/SR742	7C/SR742	1	*
P02	BOX 2	3'-0"	7'-0"	STEEL	1-3/4"	F	STEEL	7A/SR742	7B/SR742	7C/SR742	1	*
P03A	PRESS BOX	3'-0"	7'-0"	STEEL	1-3/4"	F	STEEL	7A/SR742	7B/SR742	7C/SR742	1	*
P03B	PRESS BOX	3'-0"	7'-0"	STEEL	1-3/4"	F	STEEL	7A/SR742	7B/SR742	7C/SR742	1	*
P04	BOX 4	3'-0"	7'-0"	STEEL	1-3/4"	F	STEEL	7A/SR742	7B/SR742	7C/SR742	1	*
P05	BOX 5	3'-0"	7'-0"	STEEL	1-3/4"	F	STEEL	7A/SR742	7B/SR742	7C/SR742	1	*

*NOTE: REFERENCE LS3P's DOOR HARDWARE SET LIST

3 SR-740 PRESSBOX ROOF PLAN
SCALE: 1/4" = 1'-0"

2 SR-740 PRESSBOX RCP
SCALE: 1/4" = 1'-0"

RCP LEGEND

	2'x2' ACT CEILING PANELS
	SURFACE MOUNTED LED FIXTURE
	SURFACE MOUNTED LED FIXTURE
	CEILING MOUNTED A/C UNIT

1 SR-740 ENLARGED PRESSBOX PLAN
SCALE: 1/4" = 1'-0"

SAVANNAH-CHATHAM COUNTY PUBLIC SCHOOL SYSTEM

SCCPSS

RFP C24-01 Groves Athletic Field & Fieldhouse

LS3P

321 WEST CONGRESS STREET SUITE 301
SAVANNAH, GEORGIA 31401
TEL. 912.695.2111 FAX 912.298.0206
WWW.LS3P.COM

Drawing Copyright © 2020

CHA
7 East Congress Street, Suite 306
Savannah, GA 31401
912.721.6999 • www.chacompanies.com

STATE OF GEORGIA
KARL D. LEABO
CERTIFICATE NO. 012881
REGISTERED ARCHITECT

MEMBERS OF THE AMERICAN INSTITUTE OF ARCHITECTS

COPYRIGHT 2018 ALL RIGHTS RESERVED
PRINTED OR ELECTRONIC DRAWINGS AND DOCUMENTATION MAY NOT BE REPRODUCED IN ANY FORM WITHOUT WRITTEN PERMISSION FROM LS3P ASSOCIATES LTD.

REVISIONS:

No.	Description	Date
1	Addendum 7	07/21/23

PROJECT: 5201-192070
DATE: 10/09/2020
DRAWN BY: BEB
CHECKED BY: KL

PRESSBOX ENLARGED PLANS AND DETAILS

SR-740

BID SET

V:\PROJECTS\ANY\K5\057159.000\CADD_ACAD\ARCH\03-CD\SR-740-057159.DWG
10/8/2020 3:32:55 PM