# Hardware Schedule

Project ID: 55193 - GROVES ATHLETICS BUILDINGS

## Heading #: 001 OFFICE NC WS

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F1202.2 | CORRIDOR TO ATHLETIC TRAINING | RH |
| 1 | SGL | Door: F1207 | CORRIDOR TO ADMIN | LH |
| 1 | SGL | Door: F1302.3 | CORRIDOR FROM K-9 UNIT | RHR |
| 1 | SGL | Door: F2210 | COMMAND CENTER TO PM | LH |
| 1 | SGL | Door: F2211 | COMMAND CENTER TO EMERG LT | RH |

3' 0" x 7' 0" x 1 3/4" WDD/HMF

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F1202.3 | EXTERIOR TO ATHLETIC TRAINING | LH |

3' 4" x 7' 0" x 1 3/4" HMD/HMF

| | | | | |
|---|---|---|---|---|
| 18 EA | Hinge, Full Mortise | TA2714 4-1/2" x 4-1/2" | US26D | (HI-13) McKinney |
| 6 EA | Office/Entry Lock | 21 8205 LNJ GMK | US26D | (LO-2) Sargent |
| 6 EA | Wall Stop | 409 | US32D | (ST-1) Rockwood |
| 18 EA | Silencer | 608-RKW | | (SI-1) Rockwood |

## Heading #: 003 OFFICE NC WS - SMOKE

| | | | | | |
|---|---|---|---|---|---|
| 1 | SGL | Door: F2202 | WORKROOM TO ADMIN | LH | 45 |

3' 0" x 7' 0" x 1 3/4" WDD/HMF

| | | | | |
|---|---|---|---|---|
| 3 EA | Hinge, Full Mortise | TA2714 4-1/2" x 4-1/2" | US26D | (HI-13) McKinney |
| 1 EA | Office/Entry Lock | 21 8205 LNJ GMK | US26D | (LO-2) Sargent |
| 1 EA | Surface Closer | TB 351 O | EN | (CL-4) Sargent |
| 1 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 1 EA | Wall Stop | 409 | US32D | (ST-1) Rockwood |
| 1 EA | Gasketing | S88D 17' | | (GA-6) Pemko |

## Heading #: 005 OFFICE NC - OHS

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F2209.3 | MP ROOM TO COMMAND CENTER | LH |

3' 0" x 7' 0" x 1 3/4" WDD/HMF

| | | | | |
|---|---|---|---|---|
| 3 EA | Hinge, Full Mortise | TA2714 4-1/2" x 4-1/2" | US26D | (HI-13) McKinney |
| 1 EA | Office/Entry Lock | 21 8205 LNJ GMK | US26D | (LO-2) Sargent |
| 1 EA | Surface Overhead Holder/Stop | 9-336 | 689 | (OH-1) Rixson |
| 3 EA | Silencer | 608-RKW | | (SI-1) Rockwood |

## Heading #: 011 STORAGE NC WS

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F1305.3 | CORRIDOR TO DISTRICT ATHLETIC STORAGE | RHR |
| 1 | SGL | Door: F2110.2 | RECORDS TO STORAGE | LH |
| 1 | SGL | Door: F2111 | CORRIDOR TO STORAGE | LH |
| 1 | SGL | Door: F2207.1 | OFFICE FROM CLOSET | LHR |
| 1 | SGL | Door: F2208.1 | OFFICE FROM CLOSET | LHR |
| 1 | SGL | Door: F2209.2 | COMMAND CENTER FROM STORAGE | RHR |
| 1 | SGL | Door: F2213.7 | MP ROOM TO STORAGE | RHR |
| 1 | SGL | Door: F2220 | CORRIDOR TO MEN | RH |

3' 0" x 7' 0" x 1 3/4" WDD/HMF

| | | | | |
|---|---|---|---|---|
| 24 EA | Hinge, Full Mortise | TA2714 4-1/2" x 4-1/2" | US26D | (HI-13) McKinney |
| 8 EA | Storeroom/Closet Lock | 21 8204 LNJ GMK | US26D | (LO-1) Sargent |
| 8 EA | Wall Stop | 409 | US32D | (ST-1) Rockwood |
| 24 EA | Silencer | 608-RKW | | (SI-1) Rockwood |

# Hardware Schedule

Project ID: 55193 - GROVES ATHLETICS BUILDINGS

## Heading #: 012 STORAGE CL-O- WS - SMOKE

| | | | | | |
|---|---|---|---|---|---|
| 1 | SGL | Door: F1211 | ELECTRICAL TO DATA | RH | 90 |
| 1 | SGL | Door: F2203 | CORRIDOR TO ELECTRICAL | LH | 45 |

3' 0" x 7' 0" x 1 3/4" HMD/HMF

| | | | | | |
|---|---|---|---|---|---|
| 1 | SGL | Door: F2205 | ELECTRICAL TO DATA | LH | 45 |
| 1 | SGL | Door: F2302.2 | EVIDENCE STORAGE FROM DRUGS | RH | 45 |

3' 0" x 7' 0" x 1 3/4" WDD/HMF

| | | | | |
|---|---|---|---|---|
| 12 EA | Hinge, Full Mortise | TA2714 4-1/2" x 4-1/2" | US26D | (HI-13) McKinney |
| 4 EA | Storeroom/Closet Lock | 21 8204 LNJ GMK | US26D | (LO-1) Sargent |
| 4 EA | Surface Closer | TB 351 O | EN | (CL-4) Sargent |
| 4 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 4 EA | Wall Stop | 409 | US32D | (ST-1) Rockwood |
| 4 EA | Gasketing | S88D 17' | | (GA-6) Pemko |

## Heading #: 013 STORAGE NC OHS - 3'0"

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F1204.1 | CORRIDOR TO JAN & LAUNDRY | LH |
| 1 | SGL | Door: F1302.2 | K-9 UNIT FROM STORAGE | LHR |
| 1 | SGL | Door: F2301.3 | EVIDENCE STORAGE FROM DRUGS | RHR |

3' 0" x 7' 0" x 1 3/4" WDD/HMF

| | | | | |
|---|---|---|---|---|
| 9 EA | Hinge, Full Mortise | TA2714 4-1/2" x 4-1/2" | US26D | (HI-13) McKinney |
| 3 EA | Storeroom/Closet Lock | 21 8204 LNJ GMK | US26D | (LO-1) Sargent |
| 3 EA | Surface Overhead Holder/Stop | 9-336 | 689 | (OH-1) Rixson |
| 9 EA | Silencer | 608-RKW | | (SI-1) Rockwood |

## Heading #: 033 STORAGE PR OHS

| | | | | |
|---|---|---|---|---|
| 1 | PRA/PRI | Door: F2217 | CORRIDOR FROM STORAGE | RHRA/LHR |

2-3' 2" x 7' 0" x 1 3/4" WDD/HMF

| | | | | |
|---|---|---|---|---|
| 6 EA | Hinge, Full Mortise | TA2714 4-1/2" x 4-1/2" | US26D | (HI-13) McKinney |
| 2 EA | Flush Bolt | 555 | US26D | (BO-1) Rockwood |
| 1 EA | Dust Proof Strike | 570 | US26D | (BO-2) Rockwood |
| 1 EA | Storeroom/Closet Lock | 21 8204 LNJ GMK | US26D | (LO-1) Sargent |
| 2 EA | Surface Overhead Holder/Stop | 9-336 | 689 | (OH-1) Rixson |
| 2 EA | Astragal | 29324CNB x 84" Black Brush | | (AS-1) Pemko |
| 2 EA | Silencer | 608-RKW | | (SI-1) Rockwood |

## Heading #: 034 EXT HM STORAGE SGL

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: P03A | EXTERIOR FROM PRESSBOX | LHR |
| 1 | SGL | Door: P03B | EXTERIOR FROM PRESSBOX | RHR |

3' 0" x 7' 0" x 1 3/4" By Others/By Others

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: C01 | EXTERIOR FROM JANITOR | RHR |
| 1 | SGL | Door: C02 | EXTERIOR FROM OFFICIALS ROOM 1 | LHR |
| 1 | SGL | Door: C04 | EXTERIOR FROM OFFICIALS ROOM 2 | RHR |
| 1 | SGL | Door: C06 | EXTERIOR FROM ELECTRICAL | RHR |
| 1 | SGL | Door: DG112 | EXTERIOR FROM STORAGE | RHR |
| 1 | SGL | Door: DG112A | EXTERIOR FROM STORAGE | RHR |
| 1 | SGL | Door: DG112B | ECE LAB FROM STORAGE | RHR |

3' 0" x 7' 0" x 1 3/4" HMD/HMF

| | | | | |
|---|---|---|---|---|
| 27 EA | Hinge, Full Mortise, Hvy Wt | T4A3386xNRP 4-1/2" x 4-1/2" | US32D | (HI-15) McKinney |
| 9 EA | Dormitory/Exit Lock | 10 21 8225 LNJ GMK | US32D | (LO-19) Sargent |
| 9 EA | Surface Closer | TB 351 CPS | EN | (CL-1) Sargent |
| 9 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 9 EA | Threshold | 272A x 36" MSES10 | | (TH-2) Pemko |
| 9 EA | Gasketing | 303AS x 36" x 84" TKSP | | (GA-1) Pemko |
| 9 EA | Sweep | 315CN x 36" TKSP | | (SW-1) Pemko |

# Hardware Schedule

Project ID: 55193 - GROVES ATHLETICS BUILDINGS

## Heading #: 037 EXT HM STORAGE SGL- O - DPS

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F1209 | EXTERIOR TO TICKETS | RH |
| 1 | SGL | Door: F1214 | EXTERIOR FROM TICKETS | LHR |
| 1 | SGL | Door: F1215 | EXTERIOR FROM TICKETS | RH |

3' 0" x 7' 0" x 1 3/4" HMD/HMF

| | | | | |
|---|---|---|---|---|
| 9 EA | Hinge, Full Mortise, Hvy Wt | T4A3386xNRP 4-1/2" x 4-1/2" | US32D | (HI-15) McKinney |
| 3 EA | Dormitory/Exit Lock | 10 21 8225 LNJ GMK | US32D | (LO-19) Sargent |
| 3 EA | Surface Closer | TB 351 O | EN | (CL-4) Sargent |
| 3 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 3 EA | Threshold | 272A x 36" MSES10 | | (TH-2) Pemko |
| 3 EA | Gasketing | 303AS x 36" x 84" TKSP | | (GA-1) Pemko |
| 3 EA | Sweep | 315CN x 36" TKSP | | (SW-1) Pemko |
| 3 EA | Switch | 3287 | | (EA-1) Sargent |
| 3 EA | Frame Cable | MCC-FR 75' 2 COND DPS | | (EA-3) McCarthy, Inc. |

Termination of all low voltage cables to be provided by the SCCPSS's vendor. All cables scheduled under this set shall be run to the DPS junction box. This junction box shall be located above the door in an accessible location above the ceiling, excess DPS cable shall be pulled into the junction box coiled neatly, tie wrapped together. Door is monitored for DPS only.

## Heading #: 038 EXT HM STORAGE SGL- CPS - DPS

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F103 | EXTERIOR FROM CONCESSIONS | LHR |
| 1 | SGL | Door: F104 | EXTERIOR FROM JANITOR | RHR |
| 1 | SGL | Door: F105 | EXTERIOR FROM ELEC | RHR |
| 1 | SGL | Door: F108 | EXTERIOR FROM CONCESSIONS | RHR |
| 1 | SGL | Door: F109 | EXTERIOR FROM JANITOR | LHR |
| 1 | SGL | Door: F110 | EXTERIOR FROM ELEC | LHR |
| 1 | SGL | Door: F1302.1 | EXTERIOR FROM K-9 UNIT | LHR |
| 2 | SGL | Door: PB109 | EXTERIOR FROM ELEC/MECH | RHR |
| 1 | SGL | Door: PB109A | EXTERIOR FROM ELEC/MECH | RHR |
| 2 | SGL | Door: PB111 | EXTERIOR FROM STAIR | RHR |
| 1 | SGL | Door: PB111A | EXTERIOR FROM STAIR | RHR |
| 1 | SGL | Door: RC101 | EXTERIOR FROM CONCESSIONS | RHR |
| 1 | SGL | Door: RC102 | EXTERIOR FROM STORAGE | RHR |
| 1 | SGL | Door: RC103 | EXTERIOR FROM ELECTRICAL | LHR |
| 1 | SGL | Door: RC107 | EXTERIOR FROM JANITOR | RHR |

3' 0" x 7' 0" x 1 3/4" HMD/HMF

| | | | | |
|---|---|---|---|---|
| 51 EA | Hinge, Full Mortise, Hvy Wt | T4A3386xNRP 4-1/2" x 4-1/2" | US32D | (HI-15) McKinney |
| 17 EA | Dormitory/Exit Lock | 10 21 8225 LNJ GMK | US32D | (LO-19) Sargent |
| 17 EA | Surface Closer | TB 351 CPS | EN | (CL-1) Sargent |
| 17 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 17 EA | Threshold | 272A x 36" MSES10 | | (TH-2) Pemko |
| 17 EA | Gasketing | 303AS x 36" x 84" TKSP | | (GA-1) Pemko |
| 17 EA | Sweep | 315CN x 36" TKSP | | (SW-1) Pemko |
| 17 EA | Switch | 3287 | | (EA-1) Sargent |
| 17 EA | Frame Cable | MCC-FR 75' 2 COND DPS | | (EA-3) McCarthy, Inc. |

Termination of all low voltage cables to be provided by the SCCPSS's vendor. All cables scheduled under this set shall be run to the DPS junction box. This junction box shall be located above the door in an accessible location above the ceiling, excess DPS cable shall be pulled into the junction box coiled neatly, tie wrapped together. Door is monitored for DPS only.

# Hardware Schedule

Project ID: 55193 - GROVES ATHLETICS BUILDINGS

## Heading #: 040 CLASSROOM WS

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F2101.1 | CORRIDOR TO EXECUTIVE ADMIN | LH |
| 1 | SGL | Door: F2101.2 | EXEC ADMIN FROM CHIEF | RHR |
| 1 | SGL | Door: F2101.3 | EXEC ADMIN FROM CHIEF | RHR |
| 1 | SGL | Door: F2102.1 | CORRIDOR TO CONFERENCE | LH |
| 1 | SGL | Door: F2102.2 | CORRIDOR TO CONFERENCE | RH |
| 1 | SGL | Door: F2103 | CORRIDOR FROM DC OFFICE | LH |
| 1 | SGL | Door: F2105 | CORRIDOR TO DC OFFICE | RH |
| 1 | SGL | Door: F2106 | CORRIDOR TO OPEN OFFICE | RH |
| 1 | SGL | Door: F2110.1 | CORRIDOR TO RECORDS | LH |
| 1 | SGL | Door: F2207 | CORRIDOR TO OFFICE | LH |
| 1 | SGL | Door: F2208 | CORRIDOR TO ADMIN SGT | LH |
| 1 | SGL | Door: F2215 | CORRIDOR TO OL | LH |
| 1 | SGL | Door: F2216 | CORRIDOR TO CIU/IU | LH |
| 1 | SGL | Door: F2218 | CORRIDOR TO CONFERENCE | LH |
| 1 | SGL | Door: F2303 | CORRIDOR TO SFL | RH |
| 1 | SGL | Door: F2304 | CORRIDOR TO SFL | LH |
| 1 | SGL | Door: F2305 | CORRIDOR TO OL | RH |
| 1 | SGL | Door: F2306 | CORRIDOR TO CUSTODIAN | LH |
| 3' 0" x 7' 0" x 1 3/4" WDD/HMF | | | | |
| 1 | SGL | Door: F2104 | CORRIDOR FROM OPEN OFFICE | LH |
| 3' 0" x 7' 1/4" x 1 3/4" ALD/ALF | | | | |

| | | | | |
|---|---|---|---|---|
| 57 EA | Hinge, Full Mortise | TA2714 4-1/2" x 4-1/2" | US26D | (HI-13) McKinney |
| 19 EA | Office/Entry Lock | 21 V01 8205 LNJ GMK | US26D | (LO-3) Sargent |
| 19 EA | Wall Stop | 409 | US32D | (ST-1) Rockwood |
| 57 EA | Silencer | 608-RKW | | (SI-1) Rockwood |

## Heading #: 041 CLASSROOM OHS

| | | | | |
|---|---|---|---|---|
| 2 | SGL | Door: PB110 | STAIR TO CONCESSIONS | LH |
| 1 | SGL | Door: PB110A | STAIR TO CONCESSIONS | LH |
| 3' 0" x 7' 0" x 1 3/4" WDD/HMF | | | | |

| | | | | |
|---|---|---|---|---|
| 9 EA | Hinge, Full Mortise | TA2714 4-1/2" x 4-1/2" | US26D | (HI-13) McKinney |
| 3 EA | Office/Entry Lock | 21 V01 8205 LNJ GMK | US26D | (LO-3) Sargent |
| 3 EA | Surface Overhead Holder/Stop | 9-336 | 689 | (OH-1) Rixson |
| 9 EA | Silencer | 608-RKW | | (SI-1) Rockwood |

## Heading #: 047 CLASSROOM O WS - RATED

| | | | | | |
|---|---|---|---|---|---|
| 1 | SGL | Door: F2206 | CORRIDOR TO WORKROOM | RH | 45 |
| 1 | SGL | Door: F2302.1 | CORRIDOR TO WORKROOM | LH | 45 |
| 3' 0" x 7' 0" x 1 3/4" WDD/HMF | | | | | |

| | | | | |
|---|---|---|---|---|
| 6 EA | Hinge, Full Mortise | TA2714 4-1/2" x 4-1/2" | US26D | (HI-13) McKinney |
| 2 EA | Office/Entry Lock | 21 V01 8205 LNJ GMK | US26D | (LO-3) Sargent |
| 2 EA | Surface Closer | TB 351 O | EN | (CL-4) Sargent |
| 2 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 2 EA | Wall Stop | 409 | US32D | (ST-1) Rockwood |
| 2 EA | Gasketing | S88D 17' | | (GA-6) Pemko |

## Heading #: 055 PRIVACY NR WS

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F1102.2 | TOILET TO VISITOR SHOWER | RH |
| 3' 0" x 7' 0" x 1 3/4" HMD/HMF | | | | |
| 1 | SGL | Door: F2212 | COMMAND CENTER TO TOILET | LH |
| 3' 0" x 7' 0" x 1 3/4" WDD/HMF | | | | |

| | | | | |
|---|---|---|---|---|
| 6 EA | Hinge, Full Mortise | TA2714 4-1/2" x 4-1/2" | US26D | (HI-13) McKinney |
| 2 EA | Privacy Lock | V20 8265 LNJ | US26D | (LO-4) Sargent |
| 2 EA | Wall Stop | 409 | US32D | (ST-1) Rockwood |
| 6 EA | Silencer | 608-RKW | | (SI-1) Rockwood |

# Hardware Schedule

Project ID: 55193 - GROVES ATHLETICS BUILDINGS

## Heading #: 056 PRIVACY CL O WS

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: C03 | OFFICIALS ROOM 1 FROM SHOWER/TOILET | LHR |
| 1 | SGL | Door: C05 | OFFICIALS ROOM 2 FROM SHOWER/TOILET | RHR |

3' 0" x 7' 0" x 1 3/4" HMD/HMF

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F1205 | CORRIDOR TO WOMEN | LH |
| 1 | SGL | Door: F1206 | CORRIDOR TO COACH LOCKER/TOILET | RH |
| 1 | SGL | Door: F1303.1 | K-9 UNIT TO TOILET | RH |
| 1 | SGL | Door: F1303.2 | K-9 UNIT TO TOILET | RH |
| 1 | SGL | Door: F2108 | CORRIDOR TO MEN | RH |
| 1 | SGL | Door: F2109 | CORRIDOR TO WOMEN | LH |

3' 0" x 7' 0" x 1 3/4" WDD/HMF

| | | | | |
|---|---|---|---|---|
| 24 EA | Hinge, Full Mortise | TA2714 4-1/2" x 4-1/2" | US26D | (HI-13) McKinney |
| 8 EA | Privacy Lock | V20 8265 LNJ | US26D | (LO-4) Sargent |
| 8 EA | Surface Closer | TB 351 O | EN | (CL-4) Sargent |
| 8 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 8 EA | Wall Stop | 409 | US32D | (ST-1) Rockwood |
| 24 EA | Silencer | 608-RKW | | (SI-1) Rockwood |

## Heading #: 058 PRIVACY NR OHS - 2'4"

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F2219.1 | CORRIDOR TO MEN | LH |
| 1 | SGL | Door: F2221.1 | CORRIDOR TO WOMEN | RH |

3' 0" x 7' 0" x 1 3/4" WDD/HMF

| | | | | |
|---|---|---|---|---|
| 6 EA | Hinge, Full Mortise | TA2714 4-1/2" x 4-1/2" | US26D | (HI-13) McKinney |
| 2 EA | Privacy Lock | V20 8265 LNJ | US26D | (LO-4) Sargent |
| 2 EA | Surface Overhead Holder/Stop | 9-136 | 689 | (OH-4) Rixson |
| 6 EA | Silencer | 608-RKW | | (SI-1) Rockwood |

## Heading #: 059 PRIVACY NR OHS - 3'

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F1203.1 | HOME TOILET TO HOME SHOWER | LH |

3' 0" x 7' 0" x 1 3/4" WDD/HMF

| | | | | |
|---|---|---|---|---|
| 3 EA | Hinge, Full Mortise | TA2714 4-1/2" x 4-1/2" | US26D | (HI-13) McKinney |
| 1 EA | Privacy Lock | V20 8265 LNJ | US26D | (LO-4) Sargent |
| 1 EA | Surface Overhead Holder/Stop | 9-336 | 689 | (OH-1) Rixson |
| 3 EA | Silencer | 608-RKW | | (SI-1) Rockwood |

## Heading #: 062 PASSAGE WS

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: P01 | PRESSBOX TO BOX 1 | LH |
| 1 | SGL | Door: P02 | PRESSBOX TO BOX 2 | RH |
| 1 | SGL | Door: P04 | PRESSBOX TO BOX 4 | LH |
| 1 | SGL | Door: P05 | PRESSBOX TO BOX 5 | RH |

3' 0" x 7' 0" x 1 3/4" By Others/By Others

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F2107 | CORRIDOR TO LOUNGE | LH |

3' 0" x 7' 0" x 1 3/4" WDD/HMF

| | | | | |
|---|---|---|---|---|
| 15 EA | Hinge, Full Mortise | TA2714 4-1/2" x 4-1/2" | US26D | (HI-13) McKinney |
| 5 EA | Passage Latch | 8215 LNJ | US26D | (LO-5) Sargent |
| 5 EA | Wall Stop | 409 | US32D | (ST-1) Rockwood |
| 15 EA | Silencer | 608-RKW | | (SI-1) Rockwood |

# Hardware Schedule

Project ID: 55193 - GROVES ATHLETICS BUILDINGS

## Heading #: 069 PP- O WS

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F2219 | CORRIDOR TO MEN | RH |
| 1 | SGL | Door: F2221 | CORRIDOR TO MEN | LH |

3' 0" x 7' 0" x 1 3/4" WDD/HMF

| | | | | |
|---|---|---|---|---|
| 6 EA | Hinge, Full Mortise | TA2714 4-1/2" x 4-1/2" | US26D | (HI-13) McKinney |
| 2 EA | Arm Pull | AP1007 | US32D-MS | (PP-1) Rockwood |
| 2 EA | Push Plate | 73C | US32D-MS | (PP-2) Rockwood |
| 2 EA | Surface Closer | TB 351 O | EN | (CL-4) Sargent |
| 2 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 2 EA | Wall Stop | 409 | US32D | (ST-1) Rockwood |
| 6 EA | Silencer | 608-RKW | | (SI-1) Rockwood |

## Heading #: 070 PP- O WS - SMOKE

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F2214.1 | CORRIDOR TO BREAK | LH |
| 1 | SGL | Door: F2214.2 | CORRIDOR TO BREAK | LH |

3' 0" x 7' 0" x 1 3/4" WDD/HMF

| | | | | |
|---|---|---|---|---|
| 6 EA | Hinge, Full Mortise | TA2714 4-1/2" x 4-1/2" | US26D | (HI-13) McKinney |
| 2 EA | Classroom Security Intruder Lock | 21 8238 LNJ GMK | US26D | (LO-16) Sargent |
| 2 EA | Surface Closer | TB 351 O | EN | (CL-4) Sargent |
| 2 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 2 EA | Wall Stop | 409 | US32D | (ST-1) Rockwood |
| 2 EA | Gasketing | S88D 17' | | (GA-6) Pemko |

## Heading #: 073 PP - CPS - SMOKE

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F1102.1 | LOBBY TO TOILET | LH |
| 1 | SGL | Door: F1102.3 | LOBBY TO TOILET | LH |

3' 0" x 7' 0" x 1 3/4" HMD/HMF

| | | | | |
|---|---|---|---|---|
| 6 EA | Hinge, Full Mortise | TA2714 4-1/2" x 4-1/2" | US26D | (HI-13) McKinney |
| 2 EA | Classroom Deadlock | 21 4877 GMK | US26D | (LO-18) Sargent |
| 2 EA | Arm Pull | AP1007 | US32D-MS | (PP-1) Rockwood |
| 2 EA | Push Plate | 73C | US32D-MS | (PP-2) Rockwood |
| 2 EA | Surface Closer | TB 351 CPS | EN | (CL-1) Sargent |
| 2 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 2 EA | Gasketing | S88D 17' | | (GA-6) Pemko |

# Hardware Schedule

Project ID: 55193 - GROVES ATHLETICS BUILDINGS

## Heading #: 077 EXT PP DEADBOLT CPS - GANG RR- DPS

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F101 | EXTERIOR FROM WOMEN | LHR |
| 1 | SGL | Door: F102 | EXTERIOR FROM MEN | RHR |
| 1 | SGL | Door: F106 | EXTERIOR FROM WOMEN | RHR |
| 1 | SGL | Door: F107 | EXTERIOR FROM MEN | LHR |
| 1 | SGL | Door: RC106 | EXTERIOR FROM MENS RESTROOM | RHR |
| 1 | SGL | Door: RC108 | EXTERIOR FROM WOMENS RESTROOM | LHR |

3' 0" x 7' 0" x 1 3/4" HMD/HMF

| | | | | |
|---|---|---|---|---|
| 18 EA | Hinge, Full Mortise, Hvy Wt | T4A3386xNRP 4-1/2" x 4-1/2" | US32D | (HI-15) McKinney |
| 6 EA | Classroom Deadlock | 10 21 4877 GMK | US26D | (LO-21) Sargent |
| 6 EA | Arm Pull | AP1007 | US32D-MS | (PP-1) Rockwood |
| 6 EA | Push Plate | 73C | US32D-MS | (PP-2) Rockwood |
| 6 EA | Surface Closer | TB 351 CPS | EN | (CL-1) Sargent |
| 6 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 6 EA | Threshold | 272A x 36" MSES10 | | (TH-2) Pemko |
| 6 EA | Gasketing | 303AS x 36" x 84" TKSP | | (GA-1) Pemko |
| 6 EA | Sweep | 315CN x 36" TKSP | | (SW-1) Pemko |
| 6 EA | Switch | 3287 | | (EA-1) Sargent |
| 6 EA | Frame Cable | MCC-FR 75' 2 COND DPS | | (EA-3) McCarthy, Inc. |

Termination of all low voltage cables to be provided by the SCCPSS's vendor. All cables scheduled under this set shall be run to the DPS junction box. This junction box shall be located above the door in an accessible location above the ceiling, excess DPS cable shall be pulled into the junction box coiled neatly, tie wrapped together. Doors are monitored for DPS only.

## Heading #: 079 ALUM EXT PR-BALCONY-MP-LOCKING

| | | | | |
|---|---|---|---|---|
| 1 | PRA/PRI | Door: F2213.3 | PATIO FROM MP ROOM | RHRA/LHR |
| 1 | PRA/PRI | Door: F2213.4 | PATIO FROM MP ROOM | RHRA/LHR |
| 1 | PRA/PRI | Door: F2213.5 | PATIO FROM MP ROOM | RHRA/LHR |

2-3' 2" x 7' 0" x 1 3/4" ALD/ALF

| | | | | |
|---|---|---|---|---|
| 18 EA | Hinge, Full Mortise, Hvy Wt | RC T4A3386 4-1/2" x 4-1/2" | US32D | (HI-16) McKinney |
| 3 EA | Multi-Point Lock | NB AD700115 ETJ | US26D | (LO-12) Sargent |
| 3 EA | Multi-Point Lock | 10 NB 21 AD701315 ETJ GMK | US26D | (LO-20) Sargent |
| 6 EA | Surface Closer | TB 351 CPS | EN | (CL-1) Sargent |
| 6 EA | Drop Plate | 351D | EN | (CL-5) Sargent |
| 6 EA | Kit | 581-2 | EN | (CL-6) Sargent |

Balance of weatherseals by the door supplier. Doors to have wide stiles to accommodate hardware application.

## Heading #: 085 ALUM SGL-MP- CL-O-WS -SMOKE

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F2209.1 | CORRIDOR TO COMMAND CENTER | RH |

3' 0" x 7' 0" x 1 3/4" ALD/ALF

| | | | | |
|---|---|---|---|---|
| 3 EA | Hinge, Full Mortise | RC TA2714 4-1/2" x 4-1/2" | US26D | (HI-23) McKinney |
| 1 EA | Multi-Point Lock | NB 21 AD701315 ETJ GMK | US26D | (LO-11) Sargent |
| 1 EA | Surface Closer | TB 351 O | EN | (CL-4) Sargent |
| 1 EA | Drop Plate | 351D | EN | (CL-5) Sargent |
| 1 EA | Kit | 581-2 | EN | (CL-6) Sargent |
| 1 EA | Wall Stop | 409 | US32D | (ST-1) Rockwood |

Balance of weatherseals by the door supplier. Doors to have wide stiles to accommodate hardware application.

# Hardware Schedule

Project ID: 55193 - GROVES ATHLETICS BUILDINGS

## Heading #: 089 ALUM PR- PANIC 13/10 -CPS

| | | | | |
|---|---|---|---|---|
| 1 | PRA/PRI | Door: F2213.1 | CORRIDOR FROM MP ROOM | RHRA/LHR |
| 1 | PRA/PRI | Door: F2213.2 | CORRIDOR FROM MP ROOM | RHRA/LHR |

2-3' 2" x 7' 0" x 1 3/4" ALD/ALF

| | | | | |
|---|---|---|---|---|
| 12 EA | Hinge, Full Mortise | RC TA2314xNRP 4-1/2" x 4-1/2" | US32D | (HI-5) McKinney |
| 2 EA | Concealed Vert Rod Exit | AD8410 EO | US32D | (ED-29) Sargent |
| 2 EA | Concealed Vert Rod Exit | 21 AD8413 ETJ GMK | US32D | (ED-28) Sargent |
| 4 EA | Surface Closer | TB 351 CPS | EN | (CL-1) Sargent |
| 4 EA | Drop Plate | 351D | EN | (CL-5) Sargent |
| 4 EA | Kit | 581-2 | EN | (CL-6) Sargent |

Balance of weatherseals by the door supplier. Doors to have wide stiles to accommodate hardware application.

## Heading #: 093 ALUM EXT ENTRY PR-10/13 - DPS ONLY

| | | | | |
|---|---|---|---|---|
| 1 | PRA/PRI | Door: F1200.1 | EXTERIOR FROM CORRIDOR | RHRA/LHR |
| 1 | PRA/PRI | Door: F1200.2 | EXTERIOR FROM CORRIDOR | RHRA/LHR |

2-3' 0" x 7' 0" x 1 3/4" ALD/ALF

| | | | | |
|---|---|---|---|---|
| 12 EA | Hinge, Full Mortise, Hvy Wt | RC T4A3386 4-1/2" x 4-1/2" | US32D | (HI-16) McKinney |
| 2 EA | Concealed Vert Rod Exit | AD8410 862 | US32D | (ED-26) Sargent |
| 2 EA | Concealed Vert Rod Exit | 10 16 21 AD8410 113 x 862 GMK | US32D | (ED-46) Sargent |
| 4 EA | Surface Closer | TB 351 CPS | EN | (CL-1) Sargent |
| 4 EA | Drop Plate | 351D | EN | (CL-5) Sargent |
| 4 EA | Kit | 581-2 | EN | (CL-6) Sargent |
| 4 EA | Switch | 3287 | | (EA-1) Sargent |
| 4 EA | Frame Cable | MCC-FR 75' 2 COND DPS | | (EA-3) McCarthy, Inc. |

Balance of weatherseals by the door supplier. Doors to have wide stiles to accommodate hardware application. Termination of all low voltage cables to be provided by the SCCPSS's vendor. All cables scheduled under this set shall be run to the DPS junction box. This junction box shall be located above the door in an accessible location above the ceiling, excess DPS cable shall be pulled into the junction box coiled neatly, tie wrapped together. Both doors are monitored for DPS only.

## Heading #: 098.1

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F2200.1 | LOBBY FROM CORRIDOR | LHR |

3' 0" x 7' 0" x 1 3/4" ALD/ALF

| | | | | |
|---|---|---|---|---|
| 2 EA | Hinge, Full Mortise | RC TA2714 4-1/2" x 4-1/2" | US26D | (HI-23) McKinney |
| 0 EA | Electric Hinge | RC TA2714-QC12 4-1/2" x 4-1/2" | US26D | (HI-24) McKinney |
| 1 EA | Rim Exit Device | 21 55 56 AD8504 ETJ GMK | US32D | (ED-55) Sargent |
| 1 EA | Surface Closer | TB 351 CPS | EN | (CL-1) Sargent |
| 1 EA | Drop Plate | 351D | EN | (CL-5) Sargent |
| 1 EA | Kit | 581-2 | EN | (CL-6) Sargent |
| 1 EA | Switch | 3287 | | (EA-1) Sargent |
| 1 EA | Frame Cable | MCC-FR 75' 12 COND 20GA | | (EA-2) McCarthy, Inc. |
| 1 EA | Frame Cable | MCC-FR 75' 2 COND DPS | | (EA-3) McCarthy, Inc. |
| 1 EA | Door Cable | MCC-DR 48" | | (EA-4) McCarthy, Inc. |
| 1 EA | Door Cable | MCC-DR 6" | | (EA-5) McCarthy, Inc. |
| 1 EA | Electronic Controls | 6005BKB00 | BLACK | (EC-2) RS2 Technologies |
| 1 EA | Power Supply | AQL6-R8E1 | | (PS-1) Securitron |

# Hardware Schedule

Project ID: 55193 - GROVES ATHLETICS BUILDINGS

## Heading #: 106 HM SGL - 82271 - SMOKE

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F2100 | CORRIDOR TO CHIEF AREA | LH |
| 1 | SGL | Door: F2101.4 | CONFERENCE TO CHIEF | LH |
| 1 | SGL | Door: F2301.1 | CORRIDOR TO EVIDENCE STORAGE | LH |
| 1 | SGL | Door: F2301.2 | CORRIDOR TO CONFERENCE | LH |

3' 0" x 7' 0" x 1 3/4" WDD/HMF

| | | | | |
|---|---|---|---|---|
| 8 EA | Hinge, Full Mortise | TA2714xNRP 4-1/2" x 4-1/2" | US26D | (HI-12) McKinney |
| 4 EA | Electric Hinge | TA2714-QC12 4-1/2" x 4-1/2" | US26D | (HI-20) McKinney |
| 4 EA | Access Control Mort Lock | 21 SN200-82271-24V LNJ GMK | US26D | (LO-8) Sargent |
| 4 EA | Surface Closer | TB 351 O | EN | (CL-4) Sargent |
| 4 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 4 EA | Wall Stop | 409 | US32D | (ST-1) Rockwood |
| 4 EA | Gasketing | S88D 17' | | (GA-6) Pemko |
| 4 EA | Frame Cable | MCC-FR 75' 12 COND 20GA | | (EA-2) McCarthy, Inc. |
| 4 EA | Door Cable | MCC-DR 48" | | (EA-4) McCarthy, Inc. |
| 4 EA | Power Supply | AQL6-R8E1 | | (PS-1) Securitron |

Integrated Wiegand card reader lockset. Provide SCCPSS standard Molex 'Plug n Play' connectivity to the QC12 hinge. Coordinate wiring with the Division 26 Subcontractor. Power supply cannot be located beyond the extents of the 75' 12-conductor cable to avoid a voltage drop. Termination of all low voltage cables to be provided by the SCCPSS's vendor. All cables scheduled under this set shall be run to the power supply location, excess coiled neatly, tie wrapped together and strapped to the wall next to the power supply. Door is monitored for REX and DPS.

## Heading #: 111 EXT HM SGL- 82271-O - FS

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F1304.3 | CORRIDOR TO FIELD MAINT EQUIP | LH |

3' 0" x 7' 0" x 1 3/4" HMD/HMF

| | | | | |
|---|---|---|---|---|
| 3 EA | Hinge, Full Mortise, Hvy Wt | T4A3386xNRP 4-1/2" x 4-1/2" | US32D | (HI-15) McKinney |
| 1 EA | Access Control Mort Lock | 10 21 SN200-82271-24V BIPS-0E LNJ GMK | US26D | (LO-7) Sargent |
| 1 EA | Surface Closer | TB 351 O | EN | (CL-4) Sargent |
| 1 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 1 EA | Door Stop | 441 EXP | US26D | (ST-2) Rockwood |
| 1 EA | Threshold | 272A x 36" MSES10 | | (TH-2) Pemko |
| 1 EA | Gasketing | 303AS x 36" x 84" TKSP | | (GA-1) Pemko |
| 1 EA | Sweep | 315CN x 36" TKSP | | (SW-1) Pemko |
| 1 EA | Frame Cable | MCC-FR 75' 12 COND 20GA | | (EA-2) McCarthy, Inc. |
| 1 EA | Door Cable | MCC-DR 48" | | (EA-4) McCarthy, Inc. |
| 1 EA | Power Supply | AQL6-R8E1 | | (PS-1) Securitron |

Integrated Wiegand card reader lockset. Provide SCCPSS standard Molex 'Plug n Play' connectivity to the QC12 hinge. Coordinate wiring with the Division 26 Subcontractor. Power supply cannot be located beyond the extents of the 75' 12-conductor cable to avoid a voltage drop. Termination of all low voltage cables to be provided by the SCCPSS's vendor. All cables scheduled under this set shall be run to the power supply location, excess coiled neatly, tie wrapped together and strapped to the wall next to the power supply. Door is monitored for REX and DPS.

## Heading #: 112.1

| | | | | | |
|---|---|---|---|---|---|
| 1 | SGL | Door: F1300.S1 | EXTERIOR FROM STAIR | RHR | 60 |

3' 0" x 7' 0" x 1 3/4" HMD/HMF

| | | | | |
|---|---|---|---|---|
| 3 EA | Hinge, Full Mortise, Hvy Wt | T4A3386xNRP 4-1/2" x 4-1/2" | US32D | (HI-15) McKinney |
| 1 EA | Rim Exit Device | 10 21 WS 8804 ETJ GMK | US32D | (ED-23) Sargent |
| 1 EA | Surface Closer | TB 351 CPS | EN | (CL-1) Sargent |
| 1 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 1 EA | Threshold | 272A x 36" MSES10 | | (TH-2) Pemko |
| 1 EA | Gasketing | 303AS x 36" x 84" TKSP | | (GA-1) Pemko |
| 1 EA | Sweep | 315CN x 36" TKSP | | (SW-1) Pemko |
| 1 EA | Switch | 3287 | | (EA-1) Sargent |
| 1 EA | Frame Cable | MCC-FR 75' 2 COND DPS | | (EA-3) McCarthy, Inc. |

# Hardware Schedule

Project ID: 55193 - GROVES ATHLETICS BUILDINGS

## Heading #: 126 HM LOBBY SGL-H1-8804- O-409

| | | | | | |
|---|---|---|---|---|---|
| 1 | SGL | Door: F2100.S | STAIR FROM CORRIDOR | RHR | 60 |
| 1 | SGL | Door: F2200.S | STAIR FROM LOBBY | LHR | 60 |
| 1 | SGL | Door: F2300.S | STAIR FROM CORRIDOR | RHR | 60 |

3' 0" x 7' 0" x 1 3/4" WDD/HMF

| | | | | |
|---|---|---|---|---|
| 6 EA | Hinge, Full Mortise | TA2714xNRP 4-1/2" x 4-1/2" | US26D | (HI-12) McKinney |
| 3 EA | Electric Hinge | TA2714-QC12 4-1/2" x 4-1/2" | US26D | (HI-20) McKinney |
| 3 EA | Rim Exit Device | 12 21 56-SN200-8804 BIPS-0E ETJ GMK | US32D | (ED-35) Sargent |
| 3 EA | Surface Closer | TB 351 O | EN | (CL-4) Sargent |
| 3 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 3 EA | Wall Stop | 409 | US32D | (ST-1) Rockwood |
| 9 EA | Silencer | 608-RKW | | (SI-1) Rockwood |
| 3 EA | Frame Cable | MCC-FR 75' 12 COND 20GA | | (EA-2) McCarthy, Inc. |
| 3 EA | Door Cable | MCC-DR 48" | | (EA-4) McCarthy, Inc. |
| 3 EA | Power Supply | AQL6-R8E1 | | (PS-1) Securitron |

Integrated Wiegand card reader exit. Provide SCCPSS standard Molex 'Plug n Play' connectivity to the QC12 hinge. Coordinate wiring with the Division 26 Subcontractor. Power supply cannot be located beyond the extents of the 75' 12-conductor cable to avoid a voltage drop. Termination of all low voltage cables to be provided by the SCCPSS's vendor. All cables scheduled under this set shall be run to the power supply location, excess coiled neatly, tie wrapped together and strapped to the wall next to the power supply. Door is monitored for REX and DPS.

## Heading #: 129 STAIR SGL CL-O WS - RATED

| | | | | | |
|---|---|---|---|---|---|
| 1 | SGL | Door: F1200.S | STAIR FROM CORRIDOR | RHR | 60 |

3' 0" x 7' 0" x 1 3/4" WDD/HMF

| | | | | |
|---|---|---|---|---|
| 3 EA | Hinge, Full Mortise | TA2714xNRP 4-1/2" x 4-1/2" | US26D | (HI-12) McKinney |
| 1 EA | Rim Exit Device | 12 8815 ETJ | US32D | (ED-19) Sargent |
| 1 EA | Surface Closer | TB 351 O | EN | (CL-4) Sargent |
| 1 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 1 EA | Wall Stop | 409 | US32D | (ST-1) Rockwood |
| 1 EA | Gasketing | S88D 17' | | (GA-6) Pemko |

## Heading #: 130.1

| | | | | | |
|---|---|---|---|---|---|
| 1 | SGL | Door: F1300.S2 | EXTERIOR FROM STAIR | LHR | 60 |

3' 0" x 7' 0" x 1 3/4" HMD/HMF

| | | | | |
|---|---|---|---|---|
| 3 EA | Hinge, Full Mortise | TA2714xNRP 4-1/2" x 4-1/2" | US26D | (HI-12) McKinney |
| 1 EA | Rim Exit Device | 12 8815 ETJ | US32D | (ED-19) Sargent |
| 1 EA | Surface Closer | TB 351 CPS | EN | (CL-1) Sargent |
| 1 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 1 EA | Gasketing | S88D 17' | | (GA-6) Pemko |

# Hardware Schedule

Project ID: 55193 - GROVES ATHLETICS BUILDINGS

## Heading #: 136 EXT STAIR SGL HM - CPS -CR

| | | | | | |
|---|---|---|---|---|---|
| 1 | SGL | Door: F1208.1 | EXTERIOR FROM ELEC | LHR | |
| 1 | SGL | Door: F1208.2 | EXTERIOR TO TEAM STORAGE | RH | |
| 1 | SGL | Door: F1210 | EXTERIOR FROM ELEC | RHR | |
| 1 | SGL | Door: F1212 | EXTERIOR FROM STORAGE | RHR | |
| 1 | SGL | Door: F1213 | EXTERIOR FROM RISER | RHR | |
| 1 | SGL | Door: F1301.1 | EXTERIOR TO ATHLETIC STORAGE | RH | |
| 1 | SGL | Door: F1305.1 | ELEC FROM EM ELEC | LHR | 90 |
| 1 | SGL | Door: F1306 | EXTERIOR FROM STORAGE | LHR | |
| 1 | SGL | Door: F1306.1 | ELECTRICAL FROM EM ELECTRICAL | LHR | 90 |

3' 0" x 7' 0" x 1 3/4" HMD/HMF

| | | | | | |
|---|---|---|---|---|---|
| 1 | SGL | Door: F1204.2 | TEAM STORAGE FROM JAN & LAUNDRY | RHR | |

3' 0" x 7' 0" x 1 3/4" WDD/HMF

| | | | | | |
|---|---|---|---|---|---|
| 1 | SGL | Door: F1304.1 | EXTERIOR TO FIELD MAINT EQUIP | LH | |

6' 4" x 7' 0" x 1 3/4" HMD/HMF

| | | | | |
|---|---|---|---|---|
| 11 EA | Electric Hinge, Hvy Wt | T4A3386-QC12 4-1/2" x 4-1/2" | US32D | (HI-6) McKinney |
| 22 EA | Hinge, Full Mortise, Hvy Wt | T4A3386xNRP 4-1/2" x 4-1/2" | US32D | (HI-15) McKinney |
| 11 EA | Rim Exit Device | 10 21 WS 56-SN200-8804 BIPS-0E ETJ GMK | US32D | (ED-4) Sargent |
| 11 EA | Surface Closer | TB 351 CPS | EN | (CL-1) Sargent |
| 11 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 11 EA | Threshold | 272A x 36" MSES10 | | (TH-2) Pemko |
| 11 EA | Gasketing | 303AS x 36" x 84" TKSP | | (GA-1) Pemko |
| 11 EA | Sweep | 315CN x 36" TKSP | | (SW-1) Pemko |
| 11 EA | Frame Cable | MCC-FR 75' 12 COND 20GA | | (EA-2) McCarthy, Inc. |
| 11 EA | Door Cable | MCC-DR 48" | | (EA-4) McCarthy, Inc. |
| 11 EA | Door Cable | MCC-DR 6" | | (EA-5) McCarthy, Inc. |
| 11 EA | Power Supply | AQL6-R8E1 | | (PS-1) Securitron |

Integrated Wiegand card reader exit with electrified latch retraction. Termination of all low voltage cables to be provided by the SCCPSS's vendor. All cables scheduled under this set shall be run to the DPS junction box. This junction box shall be located above the door in an accessible location above the ceiling, excess DPS cable shall be pulled into the junction box coiled neatly, tie wrapped together. Door is monitored for REX and DPS.

## Heading #: 141 EXT HM SGL 16-8813 - DPS

| | | | | | |
|---|---|---|---|---|---|
| 1 | SGL | Door: F1201.1 | EXTERIOR FROM VESTIBULE | LHR | |

3' 0" x 7' 0" x 1 3/4" HMD/HMF

| | | | | |
|---|---|---|---|---|
| 3 EA | Hinge, Full Mortise, Hvy Wt | T4A3386xNRP 4-1/2" x 4-1/2" | US32D | (HI-15) McKinney |
| 1 EA | Rim Exit Device | 10 16 21 WS 8813 ETJ GMK | US32D | (ED-45) Sargent |
| 1 EA | Surface Closer | TB 351 CPS | EN | (CL-1) Sargent |
| 1 EA | Kick Plate | K1050 8" x 34" | US32D | (KP-1) Rockwood |
| 1 EA | Threshold | 272A x 36" MSES10 | | (TH-2) Pemko |
| 1 EA | Gasketing | 303AS x 36" x 84" TKSP | | (GA-1) Pemko |
| 1 EA | Sweep | 315CN x 36" TKSP | | (SW-1) Pemko |
| 1 EA | Switch | 3287 | | (EA-1) Sargent |
| 1 EA | Frame Cable | MCC-FR 75' 2 COND DPS | | (EA-3) McCarthy, Inc. |

Termination of all low voltage cables to be provided by the SCCPSS's vendor. All cables scheduled under this set shall be run to the DPS junction box. This junction box shall be located above the door in an accessible location above the ceiling, excess DPS cable shall be pulled into the junction box coiled neatly, tie wrapped together. Door is monitored for DPS only.

# Hardware Schedule

Project ID: 55193 - GROVES ATHLETICS BUILDINGS

## Heading #: 142 EXT HM SGL 16-8813 - DPS-3'4"

| | | | | | |
|---|---|---|---|---|---|
| 1 | SGL | Door: F1100.S | EXTERIOR FROM STAIR | RHR | 60 |
| 1 | SGL | Door: F1101.3 | EXTERIOR FROM VISITOR LOCKER | LHR | |
| 1 | SGL | Door: F1103.2 | EXTERIOR FROM VISITOR LOCKER | RHR | |

3' 0" x 7' 0" x 1 3/4" HMD/HMF

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F1201.2 | EXTERIOR FROM VESTIBULE | LH |
| 1 | SGL | Door: F1202.1 | EXTERIOR FROM VESTIBULE | RHR |

3' 4" x 7' 0" x 1 3/4" HMD/HMF

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F1101.1 | EXTERIOR TO VESTIBULE | RH |
| 1 | SGL | Door: F1103.1 | EXTERIOR FROM VISITOR LOCKER | LHR |

3' 6" x 7' 0" x 1 3/4" HMD/HMF

| | | | | |
|---|---|---|---|---|
| 21 EA | Hinge, Full Mortise, Hvy Wt | T4A3386xNRP 4-1/2" x 4-1/2" | US32D | (HI-15) McKinney |
| 7 EA | Rim Exit Device | 10 16 21 WS 8813 ETJ GMK | US32D | (ED-45) Sargent |
| 7 EA | Surface Closer | TB 351 CPS | EN | (CL-1) Sargent |
| 7 EA | Kick Plate | K1050 8" x 38" | US32D | (KP-6) Rockwood |
| 7 EA | Threshold | 272A x 40" MSES10 | | (TH-7) Pemko |
| 7 EA | Gasketing | 303AS x 40" x 84" TKSP | | (GA-19) Pemko |
| 7 EA | Sweep | 315CN x 40" TKSP | | (SW-5) Pemko |
| 7 EA | Switch | 3287 | | (EA-1) Sargent |
| 7 EA | Frame Cable | MCC-FR 75' 2 COND DPS | | (EA-3) McCarthy, Inc. |

Termination of all low voltage cables to be provided by the SCCPSS's vendor. All cables scheduled under this set shall be run to the DPS junction box. This junction box shall be located above the door in an accessible location above the ceiling, excess DPS cable shall be pulled into the junction box coiled neatly, tie wrapped together. Door is monitored for DPS only.

## Heading #: 157 GATE - DPS

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: FG1 | EXTERIOR GATE | RHR |
| 1 | SGL | Door: FG2 | EXTERIOR GATE | RHR |

0" x 0" x 1 3/4" By Others/By Others

| | | | | |
|---|---|---|---|---|
| 2 EA | Rim Exit Device | 10 16 21 8804 ETJ GMK | US32D | (ED-47) Sargent |
| 2 EA | Switch | 3287 | | (EA-1) Sargent |
| 2 EA | Frame Cable | MCC-FR 75' 2 COND DPS | | (EA-3) McCarthy, Inc. |

Balance of hardware by door supplier.

## Heading #: 158 GATE

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: FG3 | EXTERIOR GATE | LHR |

0" x 0" x 1 3/4" By Others/By Others

| | | | | |
|---|---|---|---|---|
| 1 EA | Rim Exit Device | 10 16 21 8804 ETJ GMK | US32D | (ED-47) Sargent |

Balance of hardware by door supplier.

## Heading #: 159 ALL HW BY DOOR SUPPLIER

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F1301.2 | EXTERIOR TO/FROM ATHLETIC STORAGE | NH |
| 1 | SGL | Door: F1304.2 | EXTERIOR TO/FROM PD EQUIPMENT STORAGE | NH |
| 1 | SGL | Door: F1305.2 | EXTERIOR TO/FROM PD EQUIPMENT STORAGE | NH |

10' 0" x 9' 4" x 1 3/4" By Others/By Others

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: G1 | EXTERIOR GATE | LHR |
| 1 | SGL | Door: G2 | EXTERIOR GATE | LHR |
| 1 | SGL | Door: G3 | EXTERIOR GATE | RHR |
| 1 | SGL | Door: G4 | EXTERIOR GATE | LHR |

3' 6" x 5' 7" x 1 3/4" By Others/By Others

All hardware by door supplier.

# Hardware Schedule

Project ID: 55193 - GROVES ATHLETICS BUILDINGS

## Heading #: 163 TOILET STALLS

| | | | | |
|---|---|---|---|---|
| 1 | SGL | Door: F1203.3 | HOME TOILET TO TOILET | LH |
| 1 | SGL | Door: F1203.4 | HOME TOILET TO TOILET | LH |
| 1 | SGL | Door: F1203.5 | HOME TOILET TO TOILET | LH |
| 2' 0" x 5' 8" x 1 3/4" WDD/HMF | | | | |
| 1 | SGL | Door: F1203.2 | HOME TOILET FROM TOILET | RHR |
| 2' 7" x 5' 8" x 1 3/4" WDD/HMF | | | | |
| 1 | SGL | Door: F1102.4 | TOILET TO STALL | RH |
| 1 | SGL | Door: F1102.5 | TOILET TO STALL | RH |
| 1 | SGL | Door: F1102.6 | TOILET TO STALL | RH |
| 1 | SGL | Door: F1102.7 | TOILET TO STALL | RH |
| 1 | SGL | Door: F1102.8 | TOILET TO STALL | RH |
| 1 | SGL | Door: F1203.6 | TOILET TO STALL | LH |
| 3' 0" x 5' 8" x 1 3/4" WDD/HMF | | | | |

| | | | | |
|---|---|---|---|---|
| 30 EA | Hinge, Spring | 1502 4-1/2" x 4-1/2" | US26D | (HI-25) McKinney |
| 10 EA | Privacy Lock | V20 8265 LNJ | US26D | (LO-4) Sargent |
| 10 EA | Wall Stop | 409 | US32D | (ST-1) Rockwood |
| 20 EA | Silencer | 608-RKW | | (SI-1) Rockwood |